

AD-A275 960



(12)

NSWCDD/TR-92/160

DTIC
ELECTE
FEB 22 1994
S C D

**HYPERVELOCITY TUNNEL 9 MACH 10/14
CALIBRATION**

BY DAN MARREN

STRATEGIC AND SPACE SYSTEMS DEPARTMENT

31 JANUARY 1994

Approved for public release; distribution is unlimited.

SP6

94-05619



1137
CP

DTIC QUALITY INSPECTED 2



NAVAL SURFACE WARFARE CENTER

DAHLGREN DIVISION • WHITE OAK DETACHMENT

Silver Spring, Maryland 20903-5640

94-218 221

DTIC QUALITY INSPECTED 2

HYPERVELOCITY TUNNEL 9 MACH 10/14 CALIBRATION

BY DAN MARREN
STRATEGIC AND SPACE SYSTEMS DEPARTMENT

31 JANUARY 1994

Approved for public release; distribution is unlimited.

Accession For	
NTIS CRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution /	
Availability Codes	
Dist	Avail and/or Special
A-1	

NAVAL SURFACE WARFARE CENTER
DAHLGREN DIVISION • WHITE OAK DETACHMENT
Silver Spring, Maryland 20903-5640

FOREWORD

This report documents the Mach 10/14 Calibration test program (WTR 1608) performed in the Naval Surface Warfare Center White Oak Detachment (NSWCWODET) Hypervelocity Tunnel 9. The National Aerospace Plane Joint Project Office (NASP JPO) was the sponsor for this test entry. The primary objective for this test program was to supplement previous calibrations of the NSWCWODET Tunnel 9 free stream conditions.

Approved by:



R. L. SCHMIDT, Head
Strategic and Space Systems Department

ABSTRACT

This report documents the Tunnel 9 Mach 10/14 Calibration test program (WTR 1608) performed at the Naval Surface Warfare Center, White Oak, Maryland. This effort was sponsored by the National Aerospace Plane Joint Program Office (NASP JPO). Free stream flow field parameter distributions were obtained for both the Mach 10 and 14 nozzles spanning the Reynolds number range. A total of four Mach 10, and ten Mach 14 runs were performed during this test program. The test period was 7 to 22 May 1991. Results from this test entry were combined with previous test data in the final analysis. Data from the test reveal that high quality uniform flow exists and that deviations in core flow field parameters are comparable with the calibration data taken in the past.

CONTENTS

	<u>Page</u>
INTRODUCTION	1
TEST FACILITY	1
TEST HARDWARE	2
INSTRUMENTATION	2
TUNNEL INSTRUMENTATION	2
PITOT RAKE INSTRUMENTATION	2
CALIBRATION AND TEST PROCEDURES	2
PRESSURE TRANSDUCER CALIBRATION	2
RUN SETUP AND INITIATION	3
DATA ACQUISITION AND REDUCTION	3
DIGITAL FILTERS	3
MEASUREMENT UNCERTAINTY	3
RESULTS	4
PRESENTATION OF RESULTS	4
TEMPORAL UNIFORMITY	4
RADIAL SYMMETRY	5
RUN REPEATABILITY	5
COMBINING CALIBRATION RESULTS WITH TEST DATA	5
MACH 10 SPATIAL UNIFORMITY	6
DEVIATION OF PITOT PRESSURE WITH REYNOLDS NUMBER	6
FIRST WINDOW STATION	6
DEVIATIONS OF PITOT PRESSURE WITH AXIAL POSITION	6
REYNOLDS NUMBER = $20 \times 10^6 / \text{FT}$	6
MACH 14 SPATIAL UNIFORMITY	6
DEVIATIONS OF PITOT PRESSURE WITH REYNOLDS NUMBER	6
FIRST WINDOW STATION	6
SECOND WINDOW STATION	6
THIRD WINDOW STATION	6
DEVIATIONS OF PITOT PRESSURE WITH AXIAL POSITION	7
REYNOLDS NUMBER = $4.0 \times 10^6 / \text{FT}$	7
REYNOLDS NUMBER = $2.0 \times 10^6 / \text{FT}$	7
REYNOLDS NUMBER = $0.5 \times 10^6 / \text{FT}$	7
REYNOLDS NUMBER = $0.1 \times 10^6 / \text{FT}$	7

CONTENTS (Continued)

	<u>Page</u>
SUMMARY	7
REFERENCES	25
GLOSSARY	27
APPENDIX A—FREE STREAM FLOW FIELD PARAMETERS FOR ALL NOMINAL TEST CONDITIONS	A-1
DISTRIBUTION	(1)

ILLUSTRATIONS

<u>Figure</u>		<u>Page</u>
1	NSWCWODET HYPERVELOCITY WIND TUNNEL 9	8
2	TUNNEL 9 CALIBRATION SETUP	9
3	TUNNEL 9 CALIBRATION STATIONS	10
4	TUNNEL 9 SUPPLY CONDITIONS	11
5	TUNNEL 9 TEMPORAL UNIFORMITY	12
6	COMPARISON OF HORIZONTAL AND VERTICAL PROFILES	12
7	COMPARISON OF RUN REPEATABILITY	12
8	MACH 10 NORMALIZED PITOT PROFILES AT FIRST WINDOW STATION	13
9	MACH 10 NORMALIZED PITOT PROFILES AT REYNOLDS # = 20 MILLION/FT	14
10	MACH 14 NORMALIZED PITOT PROFILES AT FIRST WINDOW STATION	15
11	MACH 14 NORMALIZED PITOT PROFILES AT SECOND WINDOW STATION	16
12	MACH 14 NORMALIZED PITOT PROFILES AT THIRD WINDOW STATION	17
13	MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 4 MILLION/FT	18
14	MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 2 MILLION/FT	19
15	MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 0.5 MILLION/FT	20
16	MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 0.1 MILLION/FT	20

TABLES

<u>Table</u>		<u>Page</u>
1	HYPERVELOCITY TUNNEL 9 CAPABILITIES	21
2	TUNNEL 9 SUPPLY/PITOT PRESSURE INSTRUMENTATION	21
3	TUNNEL 9 SUPPLY TEMPERATURE INSTRUMENTATION	22
4	ESTIMATE OF MEASUREMENT UNCERTAINTY	22
5	NSWCWODET TUNNEL 9 CALIBRATION DATA	23

INTRODUCTION

Calibration of wind tunnel facilities is necessary to properly evaluate and understand the data obtained during a test program. The Naval Surface Warfare Center White Oak Detachment (NSWCWODET) Hypervelocity Tunnel 9 frequently engages in facility calibrations. When Tunnel 9 was originally brought on-line, a complete characterization of the flow was completed. Periodic tests are performed to obtain additional calibration data relative to new capabilities or specific customer needs.

The National Aerospace Plane (NASP) program is a national initiative by the Department of Defense and National Aeronautics and Space Administration (NASA). The program objective is to develop hypersonic technologies for an experimental X-30 aircraft and eventually demonstrate single-stage-to-orbit flight. This program will perform multiple tests in Tunnel 9 over a wide range of test conditions. The purpose of these experiments is to evaluate various airframe, inlet, and propulsion configurations. Discrete calibration conditions were chosen which encompassed the planned testing range for the NASP program. The test data in this report includes test conditions where calibration data was previously unavailable.

This test was designed to calibrate the uniformity of the free stream flow field parameters in the Mach 10 and Mach 14 nozzles. This effort was combined with previous tunnel calibrations to create this inclusive calibration report.

TEST FACILITY

The NSWCWODET Hypervelocity Wind Tunnel 9 is a blow-down facility which operates at Mach numbers of 8, 10, and 14. Ranges for Reynolds numbers and supply conditions are listed in Table 1.

Tunnel 9 uses nitrogen as the working fluid. The test section is over 12 feet long and 5 feet in diameter, which enables testing of large scale model configurations. A schematic of Tunnel 9 is shown in Figure 1.

During a typical run, a vertical heating vessel is used to pressurize and heat a fixed volume of nitrogen to a predetermined pressure and temperature. The test section and vacuum sphere are evacuated to a low pressure and are separated from the heater by a pair of metal diaphragms. When the nitrogen in the heater reaches the desired temperature and pressure, the diaphragms are ruptured and the gas flows from the top of the heater, expands through the contoured nozzle, into the test section at the desired test conditions. As the hot gas exits the top of the heater, cooler

nitrogen (~300°F) from three pressurized driver vessels enters the heater base. The cold gas drives the hot gas in a piston-like fashion, thereby maintaining constant conditions in the test section during the run. More detailed information concerning the facility can be obtained from Reference 1.

TEST HARDWARE

Calibration hardware for this test consisted of a fixed Pitot rake mounted on a straight sting and a traversing Pitot rake as shown in Figure 2. The fixed Pitot rake consisted of 25 Pitot pressure probes, one at the centerline of the tunnel and the others placed 2 inches apart, horizontally spanning both sides of the tunnel. A traversing mechanism was fitted with three Pitot pressure probes to survey the vertical plane of the test section. One probe was mounted at the centerline, and two probes mounted 1 inch to either side. The traversing probe surveyed from 4.3 inches above the tunnel centerline to 3.0 inches from the tunnel wall.

INSTRUMENTATION

TUNNEL INSTRUMENTATION

The instrumentation used to monitor wind tunnel supply conditions included one supply pressure transducer, two supply temperature thermocouples, and two of the Pitot rake mounted pressure transducers in the test cell. Tables 2 and 3 list the transducers and valid ranges. Both sets of thermocouples were fabricated in-house.

PITOT RAKE INSTRUMENTATION

Instrumentation for both the fixed Pitot rake and the traversing Pitot rake coincide with Table 2 for Pitot pressure. Reference 2 provides more detail on Kulite transducers. All gauges were mounted inside the rake and were connected to the taps with flexible Tygon tubing. Tubing lengths were sized to minimize pressure lag as outlined in Reference 1.

CALIBRATION AND TEST PROCEDURES

PRESSURE TRANSDUCER CALIBRATION

Calibration of the pressure instrumentation was accomplished prior to each wind tunnel run. The data system recorded transducer response during evacuation of the test cell. The test cell evacuation was accomplished in steps where the test cell pressure was held constant at each step. Typically eight calibration points were

obtained from atmospheric pressure to approximately 1 mm Hg. Two MKS Baratron type 145 transducers with ranges of 1000 and 10 mm Hg were used as calibration standards. For each transducer, output voltage was recorded and a slope and intercept were calculated using a least squares method.

RUN SETUP AND INITIATION

After the pressure transducer calibration, preheat static tares were obtained on all transducers. The heating cycle, approximately 25 minutes in duration, was then started. A final tare was obtained at the end of the heating cycle for final instrumentation intercept corrections just prior to diaphragm rupture. Once flow was established, the sequencer triggered the data acquisition, traversing probe, photographic, and other tunnel control systems.

The fixed horizontal rake was held at 0 degree angle of attack. The traversing probe started at 4.3 inches above centerline and traversed into the boundary layer to approximately 3.0 inches from the wall during steady flow conditions.

DATA ACQUISITION AND REDUCTION

Data were sampled and recorded using the NSWCWODET Data Acquisition and Recording Equipment (DARE) VI. DARE VI is a simultaneous-sample-and-hold, single-amplifier-per-channel system with ± 14 bit resolution. The input signals from all DARE channels were amplified and fed through six-pole, low-pass Bessel filters with a cutoff frequency of 50 Hz, thus eliminating high frequency background noise. Each channel was sampled at 251 Hz. Reference 1 gives a full description of the DARE VI system.

DIGITAL FILTERS

Data taken using the DARE VI were digitally filtered using a digital representation of a sixth order, low-pass Butterworth filter. Digital filtering allows the filter cutoff frequency to be chosen after recording and changed, if necessary, to eliminate erroneous noise. Spectral analysis may be performed to aid in choosing the cutoff frequency to prevent inadvertent distortion of the data. Time delays are avoided by filtering the data twice and reversing the data in time between the two applications of the filter. A more complete description of filtering techniques can be found in Reference 1. A cutoff frequency of 10 Hz was used for tunnel supply conditions, test cell Pitots, and all calibration rake Pitots.

MEASUREMENT UNCERTAINTY

Tunnel supply conditions and test cell Pitot pressure measurements were obtained. Free stream flow properties were then calculated using the fixed rake Pitot probes. Two Pitot probes were used to obtain free stream Pitot pressure. The Pitots were chosen to represent the Pitot position during aerodynamic model testing, based on their horizontal position in the test cell. Supply thermocouples and Pitot

transducers were averaged. From Reference 3, an estimate of the uncertainty of measured and derived flow quantities is given in Table 4.

RESULTS

Table 5 represents the data runs used in the calibration. Data were obtained at six axial stations in the test section. As shown in Figure 3, station 0 corresponds to the nozzle exit. Stations -1, 1, 2, and 3 correspond to the respective positions of -20, 24, 66, and 108 inches downstream of the nozzle exit. Run 2241 was run with an axial rake position of 72 inches downstream of the nozzle exit.

PRESENTATION OF RESULTS

Results from the Pitot rake surveys are presented for each test condition. Tabulated free stream flow field parameters are listed versus radial distance from the centerline in Appendix A. Pitot pressure at each probe on the Pitot rake was normalized by the average of two Pitots located at the edge of the inviscid core (PTAVG). Data from the Pitot pressure probes, supply pressure, and supply temperature were used to compute local free stream flow field parameters, based on an assumption of thermodynamic equilibrium in the isentropic core flow.⁴ Real gas effects were accounted for by computing an equivalent perfect gas supply pressure and temperature as outlined in Reference 5. Inviscid core size was determined qualitatively for each run based on the character of the profile. One horizontal profile, averaged over the useful run time run is chosen to represent each run condition. This can be accomplished based on the tunnels temporal uniformity, symmetry in horizontal and vertical planes, and run-to-run repeatability. The next sections give examples of each characteristic.

TEMPORAL UNIFORMITY

Control valves regulate the flow of hot nitrogen through the tunnel and keep relatively constant Reynolds number conditions over the total run time. For a more complete description of Tunnel 9 operation consult Reference 1. Figure 4 shows a plot of supply conditions versus time for a standard tunnel run. The diaphragms are burst and a start-up period follows where pressure and temperature are ramped to the run values. The run values are then held constant over the usable run time. To assess the degree of temporal uniformity, normalized Pitot pressure profiles were plotted at snapshots in time during a tunnel run. Figure 5 shows five normalized Pitot pressure profiles at various times during the usable run time. As shown, the profiles vary little with time, and for all conditions, observed temporal deviations were typically on the order of 1 percent or less in pressure. Based on these observations, Pitot pressure profiles were averaged during the usable run time to obtain the spatial deviations presented in the following sections.

RADIAL SYMMETRY

To check the radial symmetry in the horizontal and vertical plane of the test section, two Pitot rakes were used. For each station and Reynolds number, the local Mach number was plotted as a function of absolute distance from the centerline. The Pitot probes were mounted at 2-inch increments radially from the centerline of the tunnel. In this manner, radial asymmetric deviations can be assessed in the horizontal flow profile. For runs where traversing Pitot data were available, the radial symmetry could be investigated between the vertical and horizontal planes. Figure 6 shows an example of how radial symmetry data was analyzed. Generally, for all run conditions asymmetric deviation was 2 percent or less in pressure, where the greater deviation of fixed Pitot or traversing Pitot reading was used. Even though the traversing probe samples each point at slightly different points in time, there was good agreement with the fixed Pitot rake. Only those Pitots that fall inside the inviscid core were used for the calculation.

RUN REPEATABILITY

For each run condition, one run is selected for a representative Pitot pressure profile. Figure 7 shows a normalized Pitot pressure plot of three separate Mach 10 runs. Notice that the profiles are very repeatable from run to run. The Mach 14 nozzle exhibits similar characteristics in run repeatability.

COMBINING CALIBRATION RESULTS WITH TEST DATA

The uniformity data presented in the preceding sections of this report represent a large amount of data. The ultimate purpose for the generation of this data is to aid in the definition of the flow profile during a test program. When a model is tested aerodynamically, the Pitot calibration rake will not be installed in the test cell. Free stream conditions are calculated as described earlier based on PO , TO , and the average of two strut-mounted Pitot probes. Refer back to Figure 2 for test cell arrangement. The calibration data can provide a definition of the flow conditions throughout the nozzle. To use the calibration data in conjunction with the aerodynamic test data, the following procedure exists. Each wind tunnel data package will contain the average supply conditions and free stream flow field parameters for the run. The average free stream flow field parameters are calculated based on measured supply conditions and the average of two strut mounted Pitot probes (PTAVG). This approach assumes constant flow field parameters across the test section. If more detailed definition of the free stream flow field is required, Appendix A lists each flow field parameter as a fraction of the PTAVG calculated quantities for each run condition and axial position. For completeness, this data should be combined with the measurement uncertainty data from Table 4.

Figures 8 through 16 are included for pretest planning purposes. The uniformity for each run condition and axial station can be compared to decide on model placement in the test section.

MACH 10 SPATIAL UNIFORMITY

Deviation of Pitot Pressure With Reynolds Number

First Window Station. For Mach 10, calibration data versus Reynolds number are available only at the first window station. Pitot pressure profiles at nominal free stream Reynolds numbers of 20×10^6 , 17×10^6 , 12×10^6 , 5.5×10^6 , and 1.0×10^6 /ft are presented in Figure 8. A constant core of 40 inches was observed. The best uniformity was observed at the 20×10^6 /ft condition which is closest to the nozzle design condition.^{6,7}

Deviations of Pitot Pressure With Axial Position

Reynolds Number = 20×10^6 /ft. Mach 10 calibration data obtained as a function of axial station are available at stations 0, 1, 2, and 3. Pitot Pressure profiles at a nominal free stream Reynolds number of 20×10^6 /ft are plotted in Figure 9. The best uniformity occurred at the first window station, 24 inches downstream of the nozzle exit. The inviscid core was approximately 40 inches at all stations except the third window station. At this station the inviscid core was 32 inches. Test models are generally tested in the first two window stations at these conditions.

MACH 14 SPATIAL UNIFORMITY

Deviations of Pitot Pressure With Reynolds Number

First Window Station. At the first window station, 24 inches downstream from the nozzle exit, data were obtained at nominal free stream Reynolds numbers of 4.0×10^6 , 2.0×10^6 , 0.5×10^6 , and 0.1×10^6 /ft. Figure 10 shows local normalized Pitot pressure plotted versus radial distance from the centerline as a function of Reynolds number. As the Reynolds number increased toward the nozzle design condition, the profiles become more uniform across the test section with a lower pressure at the center 9 inches of the test section. A constant core of approximately 36 inches in diameter was observed except for the lowest Reynolds number condition where the core was 28 inches in diameter.

Second Window Station. At the second window station, 66 inches downstream from the nozzle exit, data were obtained at nominal free stream Reynolds numbers of 4.0×10^6 , 2.0×10^6 , and 0.5×10^6 /ft. Figure 11 shows local normalized Pitot pressure plotted versus radial distance from centerline as a function of Reynolds number. A constant 36-inch diameter inviscid core was observed, except for the lowest Reynolds number condition where the core was 32 inches in diameter.

Third Window Station. At the third window station, 108 inches downstream from the nozzle exit, data were obtained at nominal free stream Reynolds numbers of 4.0×10^6 , 2.0×10^6 , and 0.5×10^6 /ft. Figure 12 shows local Mach number plotted versus radial distance from the centerline as a function of Reynolds number. A constant 36-inch diameter inviscid core was observed, except for the lowest Reynolds number condition where the core was 28 inches in diameter, and the pressure drops as the centerline is approached.

Deviations of Pitot Pressure With Axial Position

Reynolds Number = $4.0 \times 10^6/\text{ft}$. Data at the maximum Reynolds number condition were obtained axially at six locations in the test section from 20 inches upstream of the nozzle exit to 108 inches downstream of the nozzle exit. Figure 13 is a plot of local normalized Pitot pressure versus radial distance from centerline at each of the six axial stations. A constant inviscid core was 36 inches in diameter. Pitot pressure was a minimum at the center of the test section for axial distances up to 48 inches. Pressure deviations at the second and third window stations were typically smaller without a dip in pressure at the center.

Reynolds Number = $2.0 \times 10^6/\text{ft}$. Data at a nominal Reynolds number of $2.0 \times 10^6/\text{ft}$ were obtained axially at three locations in the test section at 24, 66, and 108 inches downstream of the nozzle exit. Figure 14 shows a plot of local normalized Pitot pressure versus radial distance from centerline at each of the three axial stations. A constant inviscid core of 36 inches in diameter was observed. Deviations were centered about a median value, except for the first window station where the local Pitot pressure decreased as the centerline was approached.

Reynolds Number = $0.5 \times 10^6/\text{ft}$. Data at $0.5 \times 10^6/\text{ft}$ were obtained axially at three locations in the test section at 24, 66, and 108 inches downstream of the nozzle exit. Figure 15 shows a plot of local normalized Pitot pressure versus radial distance from centerline at each of the three axial stations. A constant 36-inch diameter inviscid core was observed, except for the third window position where the core was 28 inches in diameter, and the pressure drops as the centerline is approached. Deviations were centered about a median value, except for the third window station where pressure decreased as the centerline was approached.

Reynolds Number = $0.1 \times 10^6/\text{ft}$. Data at $0.1 \times 10^6/\text{ft}$ were obtained at only one station 24 inches downstream of the nozzle exit. Figure 16 shows a plot of local normalized Pitot pressure versus radial distance from the centerline. The inviscid core was 28 inches in diameter. Pitot pressure generally decreased as the centerline was approached.

SUMMARY

Calibration data obtained in NSWCWODET Hypervelocity Tunnel 9 verify that high quality uniform flow exists at Mach 10 and 14. Spatial and temporal uniformity as well as symmetry were investigated. Flow uniformity was found to be the best in the second and third window stations, with uniformity in Mach number nominally less than ± 0.75 percent. In general, higher Reynolds number free stream conditions tend to exhibit better uniformity. Calibration data from the Mach 8 and Mach 18 nozzle will be subsequently added to this report when that data becomes available.





FIGURE 1. NSWCWO DeTher Velocity Tunnel 9

**Test Cell Configuration For
Aerodynamic Model Testing**



**Test Cell Configuration For
Tunnel Calibration**




FIGURE 2. TUNNEL 9 CALIBRATION SETUP

Mach 10

Ext	1ST Window	2ND Window	3RD Window	
●	●	●	●	Re# = 20 Million/ft.
○	●	○	○	Re# = 17 Million/ft.
○	●	○	○	Re# = 12 Million/ft.
○	●	○	○	Re# = 8 Million/ft.
○	●	○	○	Re# = 1 Million/ft.

Mach 14

Ext	1ST Window	2ND Window	3RD Window	
○	●	●	●	Re# = 3.8 Million/ft.
○	●	●	●	Re# = 2.0 Million/ft.
○	●	●	●	Re# = 0.8 Million/ft.
○	●	○	○	Re# = 0.1 Million/ft.




FIGURE 3. TUNNEL 9 CALIBRATION STATIONS




FIGURE 4. TUNNEL 9 SUPPLY CONDITIONS




FIGURE 5. TUNNEL 9 TEMPORAL UNIFORMITY




FIGURE 6. COMPARISON OF HORIZONTAL AND VERTICAL PROFILES




FIGURE 7. COMPARISON OF RUN REPEATABILITY




FIGURE 8. MACH 10 NORMALIZED PITOT PROFILES AT FIRST WINDOW STATION




FIGURE 9. MACH 10 NORMALIZED PITOT PROFILES AT REYNOLDS # = 20 MILLION/FT




FIGURE 10. MACH 14 NORMALIZED PITOT PROFILES AT FIRST WINDOW STATION




FIGURE 11. MACH 14 NORMALIZED PITOT PROFILES AT SECOND WINDOW STATION




FIGURE 12. MACH 14 NORMALIZED PITOT PROFILES AT THIRD WINDOW STATION




FIGURE 13. MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 4 MILLION/FT




FIGURE 14. MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 2 MILLION/FT




FIGURE 15. MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 0.5 MILLION/FT




FIGURE 16. MACH 14 NORMALIZED PITOT PROFILES AT REYNOLDS # = 0.1 MILLION/FT

TABLE 1. HYPERVELOCITY TUNNEL 9 CAPABILITIES

Contoured Nozzle	Supply Pressure Range (psia)	Nominal Supply Temperature (°F)	Reynolds Number Range (X10 ⁶ /ft)	Run Time Range (s)
8	4,000 to 12,000	1,100	17.6 to 50.0	0.33 to 1.3
10	500 to 14,000	1,350	0.86 to 20.0	0.23 to 8
14	100 to 20,000	2,750	0.072 to 3.8	0.7 to 15

TABLE 2. TUNNEL 9 SUPPLY/PITOT PRESSURE INSTRUMENTATION

Free Stream Nominal Reynolds Number	Supply Pressure Transducer (Range)	Pitot Pressure Transducer (Range)
Mach 10		
Re# = 1 million/ft	Viatran model 304 (0 to 10,000 psia)	Kulite model XCW-093-15A (0 to 15 psia)
Re# = 7 million/ft	Viatran model 304 (0 to 10,000 psia)	Satham model PA288TC (0 to 50 psia)
Re# = 12 million/ft	Viatran model 214 (0 to 20,000 psia)	Satham model PA288TC (0 to 50 psia)
Re# = 20 million/ft	Viatran model 214 (0 to 20,000 psia)	Satham model PA288TC (0 to 50 psia)
Mach 14		
Re# = 0.1 million/ft	Satham model PA24TC (0 to 1,000 psia)	Kulite model XCW-062-5A (0 to 5 psia)
Re# = 0.5 million/ft	Viatran model 214 (0 to 50,000 psia)	Kulite model XCW-093-15A (0 to 15 psia)
Re# = 2 million/ft	Viatran model 214 (0 to 50,000 psia)	Kulite model XCW-093-15A (0 to 15 psia)
Re# = 3.8 million/ft	Viatran model 214 (0 to 50,000 psia)	Kulite model XCW-093-15A (0 to 15 psia)

TABLE 3. TUNNEL 9 SUPPLY TEMPERATURE INSTRUMENTATION

Freestream Nominal Mach Number	Supply Temperature Transducer (Range)
Mach 10	chromel /alumel (0 to 2200°F)
Mach 14	tungsten-5% rhenium/tungsten-26% (0 to 4200°F)

TABLE 4. ESTIMATE OF MEASUREMENT UNCERTAINTY

Measured Quantity	Uncertainty
P0	$\pm 0.4\%$
T0	-1.7 to +0.5%
Pitot	$\pm 0.3\%$
Derived Quantity	
Minf	-0.2 to +0.14%
Tinf	-1.9 to +0.6%
Pinf	-0.6 to +0.5%
Qinf	$\pm 0.3\%$
RHOinf	-1.6 to +0.55%
Uinf	-0.8 to +0.2%
Reinf/L	-2.6 to +0.8%

TABLE 5. NSWCWODET TUNNEL 9 CALIBRATION DATA

RUN #	MACH #	RE#/FT x 10 ⁶	AXIAL STATION (inches)	SUPPLY PRESSURE (psia)	SUPPLY TEMP (°F)	P _T AVG (psia)	P _T mean/ P _T AVG	DEVIATION IN PRESSURE ± %	CORE DIAMETER (inches)
FIRST WINDOW STATION									
1672	9.64	1.07	24	580	1140	2.07	0.979	+1% to -5.8%	40
1674	9.91	5.55	24	3600	1290	12.04	0.977	+1% to -5.2%	40
1671	10.10	11.7	24	8000	1350	26.85	0.979	+2% to -4.4%	40
1680	10.46	16.8	24	11600	1320	36.16	0.984	+2% to -4.6%	40
2248	10.45	22.7	24	14000	1255	47.14	1.00	+1% to -1.6%	40
1408	12.45	0.07	24	225	2290	0.21	0.965	+2% to -7.7%	28
2262	13.21	0.55	24	2100	2400	1.53	0.986	+4% to -4.5%	36
2267	13.70	2.03	24	8750	2500	5.79	0.980	+1% to -9.5%	36
2240	14.19	4.10	-20	20100	2660	12.66	0.981	+1% to -8.4%	36
2243	14.45	4.81	24	20200	2375	12.38	0.984	+1% to 9.5%	36
SECOND WINDOW STATION									
2259	10.37	22.0	66	14250	1320	49.10	0.982	0 to -4.6%	40
2264	13.10	0.54	66	2250	2550	1.67	0.949	0 to -9.0%	36
2265	13.70	1.83	66	9250	2700	5.96	0.979	+1% to -5.4%	36
2241	14.16	3.43	72	19500	2880	11.79	0.982	+2% to -4.3%	36
THIRD WINDOW STATION									
2260	10.43	21.8	108	14100	1300	47.33	0.991	+3.8% to -9.3%	32
2261	13.17	0.52	108	2100	2475	1.53	0.935	+1% to 10.8%	28
2269	13.68	2.01	108	9500	2650	6.24	0.967	+0 to 6.1%	36
2268	14.35	3.84	108	20000	2700	11.82	0.983	+2% to -4.3%	36

REFERENCES

1. Boyd, C., *Hypervelocity Wind Tunnel 9 Handbook*, Third Edition, NAVSWC TR 91-616, Jul 1993, NAVSWC, Silver Spring, MD.
2. Kulite Semiconductor Products Inc., *Kulite Miniature IS Silicon Diaphragm Pressure Transducer Catalog*, Bulletin KS-10000, Ridgefield, NJ.
3. NAVSWC K24-MEK Memorandum, Subj: Update on Uncertainties in Derived Tunnel Conditions, White Oak, MD, Mar 92.
4. Brahinsky, H.S., and Neel, C.A., *Tables of Equilibrium Thermodynamic Properties of Nitrogen, Volume III. Constant Entropy*, AEDC TR-69-126, Final Report, Jan 66-Jan 69, AEDC, Arnold AF Station, TN.
5. Culotta, S., and Richards, B.E., *Methods for Determining Conditions in Real Nitrogen Expanding Flows*, VKI TN 58, Feb 1970, VKI, Rhode St. Genese, Belgium.
6. Glowacki, W.J., *NOL Hypervelocity Wind Tunnel, Report No. 2: Nozzle Design*, NOLTR 71-6, Apr 1971.
7. Harris, E.L., Glowacki, W.J., *NOL Hypervelocity Wind Tunnel, Report No. 1: Aerodynamic Design*, NOLTR 71-5, Feb 1971.

GLOSSARY

a	Velocity of the local speed of sound, ft/s
CL	Centerline of wind tunnel
CP	Pressure coefficient $(P - P_{inf})/Q_{inf}$
Mach	Free stream Mach number, $Mach = U_{inf}/a$
P_{inf}	Free stream static pressure, psia
PO, P_o	Tunnel supply pressure, psia
PO1	Equivalent perfect gas supply pressure, psia
PTAVG	Average of strut mounted Pitot pressure probes, psia
PT5	Rake pressure transducer, -16 in. from CL, psia
PT21	Rake pressure transducer, 16 in. from CL, psia
PTN	Tunnel Pitot pressure, north side, psia
PTRAV	Traverse Pitot pressure transducer, psia
PTS	Tunnel Pitot pressure, south side, psia
Q_{inf}	Free stream dynamic pressure, psia
Re_{inf}/L	Free stream Reynolds number, ft^{-1}
T_{inf}	Free stream static temperature, °F
TO	Tunnel supply temperature, °F
TO1	Equivalent perfect gas supply temperature, °F
U_{inf}	Free stream velocity, ft/s

APPENDIX A
FREE STREAM FLOW FIELD PARAMETERS FOR ALL
NOMINAL TEST CONDITIONS

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1436, RUN 1408, STATION 12 inches

MACH = 12.45 P0 = 225. psia T0 = 2290. degF PTAvg = 0.21 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degR psia 1/ft ft/sec lbm/ft3 ft**1/2

12.45 0.115 92.7 1.06E-03 7.39E+04 5979. 2.99E-05 4.58E-02

NOMINAL FREESTREAM CONDITIONS

PROFILES NORMALIZED TO NOMINAL

Probe #	Dist. from center (in)	PT	M	Q	T	P	RE	U	RHO	VIP
1	-24.00	0.228	1.357	0.229	0.551	0.124	0.467	1.007	0.225	2.128
2	-22.00	0.331	1.258	0.331	0.640	0.209	0.510	1.006	0.327	1.762
3	-20.00	0.462	1.174	0.463	0.732	0.336	0.625	1.004	0.459	1.485
4	-18.00	0.633	1.100	0.633	0.831	0.523	0.757	1.003	0.630	1.265
5	-16.00	0.830	1.040	0.830	0.927	0.768	0.893	1.001	0.828	1.100
6	-14.00	0.976	1.005	0.976	0.990	0.966	0.985	1.000	0.976	1.013
7	-12.00	1.005	0.999	1.005	1.002	1.007	1.003	1.000	1.005	0.997
8	-10.00	0.980	1.004	0.980	0.992	0.972	0.988	1.000	0.980	1.011
9	-8.00	0.961	1.008	0.962	0.984	0.946	0.976	1.000	0.961	1.020
10	-6.00	0.952	1.010	0.952	0.980	0.933	0.971	1.000	0.952	1.026
11	-4.00	0.949	1.011	0.949	0.979	0.928	0.968	1.000	0.948	1.027
12	-2.00	0.938	1.013	0.939	0.975	0.914	0.962	1.000	0.938	1.033
13	0.00	0.923	1.017	0.923	0.968	0.893	0.952	1.001	0.922	1.042
14	2.00	0.932	1.015	0.932	0.972	0.906	0.958	1.000	0.932	1.037
15	4.00	0.947	1.011	0.947	0.978	0.926	0.968	1.000	0.947	1.028
16	6.00	0.962	1.008	0.962	0.984	0.947	0.977	1.000	0.962	1.020
17	8.00	0.966	1.007	0.966	0.986	0.952	0.979	1.000	0.966	1.018
18	10.00	0.972	1.006	0.972	0.988	0.960	0.983	1.000	0.971	1.015
19	12.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.003
20	14.00	1.018	0.996	1.018	1.007	1.026	1.011	1.000	1.019	0.991
21	16.00	0.938	1.013	0.938	0.974	0.913	0.962	1.000	0.937	1.033
22	18.00	0.771	1.056	0.771	0.900	0.692	0.854	1.002	0.769	1.143
23	20.00	0.598	1.113	0.598	0.812	0.483	0.731	1.003	0.595	1.302
24	22.00	0.428	1.193	0.428	0.710	0.301	0.596	1.005	0.424	1.545
25	24.00	0.207	1.384	0.207	0.530	0.108	0.383	1.008	0.204	2.235

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1436, RUN 1409, STATION 24 inches

MACH = 12.62 P0 = 95. psia T0 = 1340. degF PTAvg = 0.09 psia

MACH	QINF psia	TINF degF	NOMINAL FREESTREAM CONDITIONS				RHOINF lbm/ft3	VIP ft**1/2
			PINF psia	REINF 1/ft	UINF ft/sec			
12.62	0.050	56.7	4.48E-04	6.54E+04	4739.	2.06E-05	4.94E-02	

Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
			M	Q	T	P	RE								
1	-24.00	0.245	1.338	0.245	0.567	0.137	0.424	1.007	0.242	2.053					
2	-22.00	0.394	1.213	0.394	0.687	0.268	0.567	1.005	0.391	1.610					
3	-20.00	0.530	1.141	0.531	0.774	0.408	0.680	1.004	0.527	1.384					
4	-18.00	0.684	1.082	0.685	0.858	0.585	0.794	1.002	0.682	1.215					
5	-16.00	0.854	1.034	0.854	0.938	0.799	0.908	1.001	0.852	1.085					
6	-14.00	0.953	1.010	0.953	0.981	0.934	0.971	1.000	0.952	1.025					
7	-12.00	0.994	1.001	0.994	0.998	0.992	0.997	1.000	0.994	1.003					
8	-10.00	0.993	1.002	0.993	0.997	0.990	0.996	1.000	0.993	1.004					
9	-8.00	0.961	1.008	0.961	0.984	0.946	0.976	1.000	0.961	1.020					
10	-6.00	0.902	1.022	0.902	0.959	0.864	0.939	1.001	0.901	1.054					
11	-4.00	0.846	1.035	0.846	0.935	0.789	0.903	1.001	0.845	1.090					
12	-2.00	0.824	1.041	0.824	0.925	0.760	0.889	1.001	0.822	1.105					
13	0.00	0.823	1.041	0.824	0.924	0.760	0.888	1.001	0.822	1.105					
14	2.00	0.837	1.038	0.837	0.930	0.777	0.897	1.001	0.835	1.096					
15	4.00	0.842	1.036	0.842	0.933	0.784	0.901	1.001	0.840	1.092					
16	6.00	0.876	1.028	0.876	0.948	0.829	0.923	1.001	0.875	1.070					
17	8.00	0.934	1.014	0.934	0.973	0.908	0.959	1.000	0.933	1.036					
18	10.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.985	1.007					
19	12.00	1.006	0.999	1.006	1.002	1.008	1.003	1.000	1.006	0.997					
20	14.00	1.001	1.000	1.001	1.000	1.001	1.000	1.000	1.001	1.000					
21	16.00	0.956	1.009	0.956	0.982	0.939	0.973	1.000	0.956	1.023					
22	18.00	0.825	1.041	0.825	0.925	0.761	0.889	1.001	0.823	1.104					
23	20.00	0.665	1.089	0.665	0.848	0.561	0.780	1.002	0.662	1.233					
24	22.00	0.485	1.162	0.485	0.746	0.359	0.643	1.004	0.481	1.449					
25	24.00	0.059	1.784	0.060	0.321	0.019	0.179	1.011	0.058	4.212					

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1436, RUN 1411, STATION 24 inches

MACH = 12.96 P0 = 290. psia T0 = 2000. degF PTAvg = 0.23 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP
psia degR psia 1/ft ft/sec lbm/ft3 ft**1/2

12.96 0.127 75.9 1.08E-03 1.05E+05 5630. 3.71E-05 4.00E-02

Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL					RE	U	RHO	VIP
			M	Q	T	P					
1	-24.00	0.317	1.268	0.318	0.629	0.198	0.497	1.006	0.314	1.798	
2	-22.00	0.451	1.179	0.451	0.725	0.324	0.616	1.004	0.448	1.503	
3	-20.00	0.631	1.100	0.631	0.830	0.521	0.755	1.003	0.628	1.266	
4	-18.00	0.828	1.040	0.828	0.927	0.766	0.892	1.001	0.827	1.101	
5	-16.00	0.987	1.003	0.987	0.995	0.981	0.992	1.000	0.987	1.007	
6	-14.00	1.039	0.992	1.039	1.016	1.055	1.023	1.000	1.039	0.981	
7	-12.00	1.006	0.999	1.006	1.002	1.008	1.004	1.000	1.006	0.997	
8	-10.00	0.968	1.007	0.968	0.987	0.956	0.981	1.000	0.968	1.017	
9	-8.00	0.956	1.009	0.956	0.982	0.939	0.973	1.000	0.956	1.023	
10	-6.00	0.951	1.011	0.951	0.980	0.931	0.970	1.000	0.950	1.026	
11	-4.00	0.957	1.009	0.957	0.982	0.940	0.974	1.000	0.956	1.023	
12	-2.00	0.950	1.011	0.951	0.980	0.931	0.970	1.000	0.950	1.026	
13	0.00	0.943	1.012	0.943	0.977	0.921	0.965	1.000	0.943	1.030	
14	2.00	0.949	1.011	0.949	0.979	0.928	0.968	1.000	0.948	1.027	
15	4.00	0.960	1.009	0.960	0.984	0.944	0.975	1.000	0.959	1.021	
16	6.00	0.974	1.006	0.974	0.989	0.963	0.984	1.000	0.973	1.014	
17	8.00	0.976	1.005	0.976	0.990	0.966	0.985	1.000	0.976	1.012	
18	10.00	0.975	1.005	0.975	0.990	0.965	0.985	1.000	0.975	1.013	
19	12.00	0.994	1.001	0.994	0.998	0.992	0.996	1.000	0.994	1.003	
20	14.00	1.047	0.990	1.047	1.019	1.067	1.028	1.000	1.048	0.977	
21	16.00	1.064	0.987	1.064	1.025	1.092	1.039	1.000	1.065	0.969	
22	18.00	0.971	1.006	0.971	0.988	0.959	0.982	1.000	0.971	1.015	
23	20.00	0.794	1.049	0.794	0.911	0.721	0.869	1.001	0.792	1.126	
24	22.00	0.581	1.119	0.581	0.803	0.464	0.718	1.003	0.578	1.321	
25	24.00	0.539	1.137	0.539	0.779	0.417	0.686	1.003	0.536	1.372	

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1669, STATION 24 inches

MACH = 9.91 P0 = 3500. psia T0 = 1290. degF PTAvg = 11.65 psia

MACH	QINF psia	TINF degr	NOMINAL FREESTREAM CONDITIONS					RHOINF lbm/ft3	VIP ft**1/2	
			PINF psia	REINF 1/ft	UINF ft/sec	P	RE			
9.91	6.313	89.1	9.18E-02	5.38E+06	4666.	2.69E-03	4.27E-03			
Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL					U	RHO	VIP
			M	Q	T	P	RE			
1	-24.00	0.800	1.049	0.800	0.913	0.727	0.873	1.002	0.796	1.123
2	-22.00	0.968	1.007	0.968	0.987	0.954	0.980	1.000	0.967	1.017
3	-20.00	1.004	0.999	1.004	1.002	1.006	1.002	1.000	1.004	0.998
4	-18.00	0.993	1.002	0.993	0.997	0.990	0.996	1.000	0.993	1.004
5	-16.00	0.994	1.001	0.994	0.997	0.991	0.996	1.000	0.993	1.003
6	-14.00	0.981	1.004	0.981	0.992	0.973	0.988	1.000	0.980	1.010
7	-12.00	0.987	1.003	0.987	0.995	0.981	0.992	1.000	0.986	1.007
8	-10.00	0.976	1.005	0.976	0.990	0.967	0.986	1.000	0.976	1.012
9	-8.00	0.973	1.006	0.973	0.989	0.962	0.983	1.000	0.972	1.014
10	-6.00	0.972	1.006	0.972	0.989	0.960	0.983	1.000	0.972	1.015
11	-4.00	0.956	1.010	0.956	0.982	0.938	0.973	1.000	0.955	1.024
12	-2.00	0.954	1.010	0.954	0.981	0.935	0.972	1.000	0.953	1.025
13	0.00	0.962	1.008	0.962	0.984	0.946	0.977	1.000	0.961	1.020
14	2.00	0.952	1.010	0.952	0.980	0.933	0.971	1.001	0.951	1.026
15	4.00	0.957	1.010	0.957	0.982	0.939	0.973	1.000	0.956	1.023
16	6.00	0.973	1.006	0.973	0.989	0.962	0.983	1.000	0.972	1.014
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
18	10.00	0.975	1.006	0.975	0.990	0.964	0.984	1.000	0.974	1.013
19	12.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.986	1.007
20	14.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.986	1.007
21	16.00	1.000	1.000	1.000	1.000	1.001	1.000	1.000	1.000	1.000
22	18.00	1.007	0.998	1.007	1.003	1.010	1.004	1.000	1.007	0.996
23	20.00	1.012	0.997	1.012	1.005	1.018	1.008	1.000	1.013	0.994
24	22.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.986	1.007
25	24.00	0.821	1.043	0.821	0.923	0.755	0.887	1.002	0.818	1.108

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1670, STATION 24 inches

MACH = 10.59 P0 = 7250. psia T0 = 1340. degF PTAvg = 19.20 psia

MACH	QINF psia	NOMINAL FREESTREAM CONDITIONS					VIP ft**1/2
		TINF degR	PINF psia	REINF 1/ft	UINF ft/sec	RHOINF lbm/ft3	
10.59	10.408	82.6	1.33E-01	9.29E+06	4799.	4.18E-03	3.47E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										RHO	U	VIP
		PT	M	Q	T	P	RE							
1	-24.00	1.045	0.991	1.045	1.018	1.065	1.027	1.000	1.046	0.977				
2	-22.00	1.220	0.959	1.220	1.084	1.327	1.129	0.998	1.224	0.902				
3	-20.00	1.107	0.979	1.107	1.042	1.156	1.064	0.999	1.109	0.949				
4	-18.00	1.010	0.998	1.010	1.004	1.014	1.006	1.000	1.010	0.995				
5	-16.00	1.296	0.946	1.296	1.111	1.447	1.171	0.998	1.302	0.874				
6	-14.00	1.265	0.951	1.265	1.101	1.398	1.154	0.998	1.271	0.885				
7	-12.00	1.262	0.952	1.262	1.099	1.393	1.152	0.998	1.267	0.886				
8	-10.00	1.247	0.954	1.246	1.094	1.369	1.144	0.998	1.251	0.892				
9	-8.00	1.255	0.953	1.255	1.097	1.383	1.149	0.998	1.260	0.889				
10	-6.00	1.258	0.952	1.258	1.098	1.387	1.150	0.998	1.263	0.888				
11	-4.00	1.231	0.957	1.231	1.088	1.345	1.135	0.998	1.236	0.898				
12	-2.00	1.229	0.957	1.229	1.088	1.342	1.134	0.998	1.234	0.899				
13	0.00	1.232	0.956	1.232	1.089	1.347	1.136	0.998	1.237	0.897				
14	2.00	1.233	0.956	1.233	1.089	1.348	1.136	0.998	1.238	0.897				
15	4.00	1.236	0.956	1.235	1.090	1.352	1.138	0.998	1.240	0.896				
16	6.00	1.246	0.954	1.246	1.094	1.368	1.143	0.998	1.251	0.892				
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000				
18	10.00	1.251	0.953	1.251	1.096	1.376	1.146	0.998	1.256	0.890				
19	12.00	1.270	0.950	1.270	1.102	1.406	1.157	0.998	1.275	0.884				
20	14.00	1.266	0.951	1.266	1.101	1.400	1.155	0.998	1.272	0.885				
21	16.00	1.292	0.947	1.291	1.110	1.440	1.169	0.998	1.298	0.876				
22	18.00	0.990	1.002	0.990	0.996	0.986	0.994	1.000	0.990	1.005				
23	20.00	1.174	0.966	1.174	1.068	1.257	1.103	0.998	1.177	0.920				
24	22.00	1.122	0.976	1.121	1.048	1.177	1.072	0.999	1.124	0.942				
25	24.00	0.997	1.001	0.997	0.999	0.995	0.998	1.000	0.997	1.002				

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1671, STATION 24 inches

MACH = 10.10 P0 = 8000. psia T0 = 1350. degF PTAvg = 26.85 psia

MACH	QINF psia	NOMINAL FREESTREAM CONDITIONS				RHOINF lbm/ft3	VIP ft**1/2
		TINF degR	PINF psia	REINF 1/ft	UINF ft/sec		
10.10	14.544	91.2	2.03E-01	1.17E+07	4813.	5.81E-03	2.95E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
		PT	M	Q	T	P	RE							
1	-24.00	0.802	1.048	0.802	0.914	0.730	0.874	1.002	0.799	1.121				
2	-22.00	0.977	1.005	0.977	0.991	0.968	0.986	1.000	0.977	1.012				
3	-20.00	1.018	0.996	1.018	1.007	1.025	1.011	1.000	1.018	0.991				
4	-18.00	1.006	0.999	1.006	1.002	1.008	1.004	1.000	1.006	0.997				
5	-16.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	0.999				
6	-14.00	0.977	1.005	0.977	0.991	0.963	0.986	1.000	0.977	1.012				
7	-12.00	0.973	1.006	0.973	0.989	0.962	0.983	1.000	0.973	1.014				
8	-10.00	0.967	1.007	0.967	0.987	0.954	0.980	1.000	0.967	1.017				
9	-8.00	0.975	1.005	0.975	0.990	0.965	0.985	1.000	0.975	1.013				
10	-6.00	0.976	1.005	0.976	0.990	0.966	0.985	1.000	0.976	1.013				
11	-4.00	0.962	1.008	0.962	0.984	0.947	0.977	1.000	0.962	1.020				
12	-2.00	0.956	1.010	0.956	0.982	0.938	0.973	1.000	0.955	1.024				
13	0.00	0.964	1.008	0.964	0.985	0.950	0.978	1.000	0.964	1.019				
14	2.00	0.958	1.009	0.958	0.983	0.941	0.974	1.000	0.957	1.022				
15	4.00	0.964	1.008	0.964	0.985	0.949	0.978	1.000	0.963	1.019				
16	6.00	0.964	1.008	0.964	0.985	0.949	0.978	1.000	0.963	1.019				
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000				
18	10.00	0.967	1.007	0.967	0.987	0.954	0.980	1.000	0.967	1.017				
19	12.00	0.974	1.006	0.974	0.989	0.963	0.984	1.000	0.974	1.014				
20	14.00	0.977	1.005	0.977	0.991	0.968	0.986	1.000	0.977	1.012				
21	16.00	0.993	1.002	0.993	0.997	0.990	0.996	1.000	0.993	1.004				
22	18.00	0.994	1.001	0.994	0.998	0.992	0.996	1.000	0.994	1.003				
23	20.00	1.011	0.998	1.011	1.005	1.016	1.007	1.000	1.012	0.994				
24	22.00	0.992	1.002	0.992	0.997	0.988	0.995	1.000	0.991	1.004				
25	24.00	0.844	1.037	0.845	0.934	0.786	0.902	1.002	0.842	1.091				

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1672, STATION 24 inches

MACH = 9.64 P0 = 580. psia T0 = 1140. degF PTAvg = 2.07 psia

MACH	QINF psia	TINF degR	NOMINAL FREESTREAM CONDITIONS				RHOINF lbm/ft3	VIP ft**1/2
			PINF psia	REINF 1/ft	UINF ft/sec	U		
9.64	1.123	84.0	1.73E-02	1.07E+06	4405.	5.36E-04	9.30E-03	

Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL							RHO	VIP
			M	Q	T	P	RE	U			
1	-24.00	0.635	1.102	0.635	0.831	0.523	0.758	1.005	0.629	1.266	
2	-22.00	0.855	1.034	0.855	0.938	0.799	0.909	1.002	0.852	1.085	
3	-20.00	0.980	1.004	0.980	0.992	0.971	0.988	1.000	0.979	1.011	
4	-18.00	0.994	1.001	0.994	0.997	0.991	0.996	1.000	0.994	1.003	
5	-16.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.986	1.007	
6	-14.00	0.976	1.005	0.976	0.990	0.966	0.985	1.000	0.975	1.013	
7	-12.00	0.976	1.005	0.976	0.990	0.966	0.985	1.000	0.975	1.013	
8	-10.00	0.977	1.005	0.977	0.990	0.967	0.986	1.000	0.976	1.012	
9	-8.00	0.979	1.005	0.979	0.991	0.971	0.987	1.000	0.979	1.011	
10	-6.00	0.979	1.005	0.979	0.991	0.970	0.987	1.000	0.978	1.011	
11	-4.00	0.967	1.007	0.967	0.986	0.954	0.980	1.000	0.967	1.017	
12	-2.00	0.969	1.007	0.969	0.987	0.956	0.981	1.000	0.969	1.016	
13	0.00	0.972	1.006	0.972	0.988	0.960	0.983	1.000	0.971	1.015	
14	2.00	0.971	1.006	0.971	0.988	0.959	0.982	1.000	0.970	1.015	
15	4.00	0.966	1.008	0.966	0.986	0.951	0.979	1.000	0.965	1.018	
16	6.00	0.979	1.005	0.979	0.991	0.971	0.987	1.000	0.979	1.011	
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
18	10.00	0.979	1.005	0.979	0.991	0.971	0.987	1.000	0.979	1.011	
19	12.00	0.942	1.013	0.942	0.976	0.918	0.964	1.001	0.941	1.031	
20	14.00	0.990	1.002	0.990	0.996	0.986	0.994	1.000	0.990	1.005	
21	16.00	0.996	1.001	0.996	0.998	0.994	0.998	1.000	0.996	1.002	
22	18.00	1.006	0.999	1.006	1.003	1.009	1.004	1.000	1.006	0.997	
23	20.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.003	
24	22.00	0.883	1.027	0.883	0.951	0.838	0.927	1.001	0.881	1.067	
25	24.00	0.646	1.098	0.646	0.837	0.536	0.766	1.004	0.640	1.255	

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1674, STATION 24 inches

MACH = 9.91 P0 = 3600. psia T0 = 1290. degF PTAvg = 12.04 psia

MACH	QINF psia	NOMINAL FREESTREAM CONDITIONS					VIP ft**1/2
		TINF degr	PINF psia	REINF 1/ft	UINF ft/sec	RHOINF lbm/ft3	
9.91	6.522	89.2	9.49E-02	5.55E+06	4667.	2.77E-03	4.21E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
		PT	M	Q	T	P	RE							
1	-24.00	0.760	1.060	0.760	0.894	0.676	0.846	1.003	0.756	1.153				
2	-22.00	0.949	1.011	0.949	0.979	0.927	0.968	1.001	0.948	1.028				
3	-20.00	0.999	1.000	0.999	1.000	0.999	0.999	1.000	0.999	1.000				
4	-18.00	0.991	1.002	0.991	0.996	0.987	0.994	1.000	0.991	1.005				
5	-16.00	0.990	1.002	0.990	0.996	0.986	0.994	1.000	0.990	1.005				
6	-14.00	0.975	1.005	0.975	0.990	0.965	0.985	1.000	0.975	1.013				
7	-12.00	0.983	1.004	0.983	0.993	0.975	0.989	1.000	0.982	1.009				
8	-10.00	0.971	1.006	0.971	0.988	0.959	0.982	1.000	0.970	1.015				
9	-8.00	0.968	1.007	0.968	0.987	0.955	0.981	1.000	0.968	1.017				
10	-6.00	0.966	1.007	0.966	0.986	0.952	0.979	1.000	0.965	1.018				
11	-4.00	0.949	1.011	0.949	0.979	0.929	0.969	1.001	0.948	1.027				
12	-2.00	0.950	1.011	0.950	0.979	0.930	0.969	1.001	0.949	1.027				
13	0.00	0.953	1.010	0.954	0.981	0.934	0.971	1.000	0.953	1.025				
14	2.00	0.948	1.012	0.948	0.978	0.926	0.968	1.001	0.947	1.028				
15	4.00	0.953	1.010	0.953	0.980	0.933	0.971	1.000	0.952	1.025				
16	6.00	0.965	1.008	0.965	0.986	0.951	0.979	1.000	0.964	1.019				
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000				
18	10.00	0.971	1.006	0.971	0.988	0.959	0.982	1.000	0.970	1.015				
19	12.00	0.987	1.003	0.987	0.995	0.981	0.992	1.000	0.986	1.007				
20	14.00	0.987	1.003	0.987	0.995	0.981	0.992	1.000	0.986	1.007				
21	16.00	1.002	0.999	1.002	1.001	1.004	1.002	1.000	1.003	0.999				
22	18.00	1.009	0.998	1.009	1.004	1.013	1.006	1.000	1.009	0.995				
23	20.00	1.014	0.997	1.014	1.006	1.020	1.009	1.000	1.014	0.993				
24	22.00	0.981	1.004	0.981	0.992	0.973	0.988	1.000	0.981	1.010				
25	24.00	0.791	1.051	0.791	0.909	0.716	0.867	1.002	0.788	1.129				

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1678, STATION 24 inches

MACH = 10.23 P0 = 8250. psia T0 = 1350. degF PTAvg = 26.31 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degr psia 1/ft ft/sec lbm/ft3 ft**1/2

10.23 14.255 89.3 1.95E-01 1.17E+07 4819. 5.68E-03 2.98E-03

NOMINAL FREESTREAM CONDITIONS

PROFILES NORMALIZED TO NOMINAL

Probe #	Dist. from center (in)	PT	M	Q	T	P	RE	U	RHO	VIP
1	-24.00	0.797	1.049	0.798	0.912	0.724	0.871	1.002	0.794	1.124
2	-22.00	0.968	1.007	0.968	0.987	0.954	0.980	1.000	0.967	1.017
3	-20.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
4	-18.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	0.999
5	-16.00	0.993	1.001	0.993	0.997	0.990	0.996	1.000	0.993	1.004
6	-14.00	0.972	1.006	0.972	0.988	0.960	0.983	1.000	0.971	1.015
7	-12.00	0.970	1.006	0.970	0.988	0.958	0.982	1.000	0.970	1.016
8	-10.00	0.962	1.008	0.962	0.984	0.946	0.976	1.000	0.961	1.020
9	-8.00	0.965	1.008	0.965	0.986	0.951	0.979	1.000	0.965	1.018
10	-6.00	0.969	1.007	0.969	0.987	0.956	0.981	1.000	0.969	1.016
11	-4.00	0.951	1.011	0.951	0.980	0.931	0.970	1.000	0.950	1.026
12	-2.00	0.948	1.011	0.948	0.978	0.927	0.968	1.001	0.947	1.028
13	0.00	0.950	1.011	0.950	0.979	0.929	0.969	1.000	0.949	1.027
14	2.00	0.951	1.011	0.951	0.980	0.930	0.970	1.000	0.950	1.027
15	4.00	0.954	1.010	0.954	0.981	0.936	0.972	1.000	0.954	1.024
16	6.00	0.962	1.008	0.962	0.984	0.946	0.977	1.000	0.961	1.020
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
18	10.00	0.967	1.007	0.967	0.986	0.953	0.979	1.000	0.966	1.018
19	12.00	0.977	1.005	0.977	0.991	0.968	0.986	1.000	0.977	1.012
20	14.00	0.975	1.005	0.975	0.990	0.965	0.985	1.000	0.975	1.013
21	16.00	0.952	1.002	0.992	0.997	0.988	0.995	1.000	0.991	1.004
22	18.00	0.997	1.001	0.997	0.999	0.996	0.998	1.000	0.997	1.001
23	20.00	1.014	0.997	1.014	1.006	1.020	1.008	1.000	1.014	0.993
24	22.00	0.994	1.001	0.994	0.997	0.991	0.996	1.000	0.993	1.003
25	24.00	0.834	1.040	0.834	0.929	0.772	0.895	1.002	0.831	1.099

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1679, STATION 24 inches

MACH = 10.16 P0 = 7800. psia T0 = 1300. degF PTAvg = 25.60 psia

MACH	QINF psia	TINF degF	NOMINAL FREESTREAM CONDITIONS				RHOINF lbm/ft3	VIP ft**1/2
			PINF psia	REINF 1/ft	UINF ft/sec	U		
10.16	13.872	87.5	1.92E-01	1.18E+07	4740.	5.72E-03	2.95E-03	

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL									
		PT	M	Q	T	P	RE	U	RHO	VIP	
1	-24.00	0.787	1.052	0.787	0.907	0.710	0.864	1.002	0.783	1.132	
2	-22.00	0.964	1.008	0.964	0.985	0.949	0.978	1.000	0.964	1.019	
3	-20.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
4	-18.00	1.008	0.998	1.008	1.003	1.011	1.005	1.000	1.008	0.996	
5	-16.00	0.994	1.001	0.994	0.998	0.991	0.996	1.000	0.994	1.003	
6	-14.00	0.970	1.007	0.970	0.988	0.957	0.981	1.000	0.969	1.016	
7	-12.00	0.966	1.007	0.966	0.986	0.952	0.979	1.000	0.966	1.018	
8	-10.00	0.955	1.010	0.955	0.982	0.937	0.972	1.000	0.954	1.024	
9	-8.00	0.957	1.009	0.957	0.982	0.940	0.974	1.000	0.956	1.023	
10	-6.00	0.959	1.009	0.959	0.983	0.942	0.975	1.000	0.958	1.022	
11	-4.00	0.942	1.013	0.942	0.976	0.919	0.964	1.001	0.941	1.031	
12	-2.00	0.938	1.014	0.938	0.974	0.913	0.962	1.001	0.937	1.034	
13	0.00	0.940	1.013	0.940	0.975	0.915	0.963	1.001	0.939	1.033	
14	2.00	0.939	1.013	0.939	0.975	0.915	0.963	1.001	0.938	1.033	
15	4.00	0.944	1.012	0.944	0.977	0.921	0.965	1.001	0.943	1.031	
16	6.00	0.952	1.011	0.952	0.980	0.932	0.970	1.000	0.951	1.026	
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
18	10.00	0.955	1.010	0.955	0.982	0.937	0.972	1.000	0.954	1.024	
19	12.00	0.965	1.008	0.965	0.986	0.951	0.979	1.000	0.954	1.018	
20	14.00	0.965	1.008	0.965	0.985	0.950	0.978	1.000	0.954	1.019	
21	16.00	0.984	1.003	0.984	0.993	0.977	0.990	1.000	0.983	1.009	
22	18.00	0.992	1.002	0.992	0.997	0.989	0.995	1.000	0.992	1.004	
23	20.00	1.009	0.998	1.009	1.004	1.013	1.006	1.000	1.009	0.995	
24	22.00	0.978	1.005	0.978	0.991	0.968	0.986	1.000	0.977	1.012	
25	24.00	0.801	1.048	0.802	0.914	0.730	0.874	1.002	0.798	1.121	

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1459, RUN 1680, STATION 24 inches

MACH = 10.46 P0 = 11600. psia T0 = 1320. degF PTAvg = 36.16 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degr psia 1/ft ft/sec lbm/ft3 ft**1/2

10.46 19.595 85.6 2.56E-01 1.68E+07 4825. 7.79E-03 2.55E-03

NOMINAL FREESTREAM CONDITIONS

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
		PT	M	Q	T	P	RE							
1	-24.00	0.774	1.056	0.774	0.901	0.695	0.855	1.002	0.771	1.002	0.771	1.142		
2	-22.00	0.960	1.009	0.960	0.983	0.943	0.975	1.000	0.959	1.000	0.959	1.021		
3	-20.00	1.016	0.997	1.016	1.006	1.023	1.010	1.000	1.016	1.000	1.016	0.992		
4	-18.00	1.004	0.999	1.004	1.002	1.006	1.003	1.000	1.005	1.000	1.005	0.998		
5	-16.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	1.000	1.003	0.999		
6	-14.00	0.997	1.001	0.997	0.999	0.996	0.998	1.000	0.997	1.000	0.997	1.002		
7	-12.00	0.989	1.002	0.990	0.996	0.985	0.994	1.000	0.989	1.000	0.989	1.005		
8	-10.00	0.976	1.005	0.977	0.990	0.967	0.986	1.000	0.976	1.000	0.976	1.012		
9	-8.00	0.980	1.004	0.980	0.992	0.971	0.987	1.000	0.979	1.000	0.979	1.011		
10	-6.00	0.972	1.006	0.972	0.988	0.960	0.983	1.000	0.971	1.000	0.971	1.015		
11	-4.00	0.963	1.008	0.963	0.985	0.948	0.977	1.000	0.963	1.000	0.963	1.020		
12	-2.00	0.954	1.010	0.954	0.981	0.935	0.972	1.000	0.953	1.000	0.953	1.025		
13	0.00	0.959	1.009	0.959	0.983	0.941	0.975	1.000	0.958	1.000	0.958	1.022		
14	2.00	0.955	1.010	0.955	0.981	0.936	0.972	1.000	0.954	1.000	0.954	1.024		
15	4.00	0.967	1.007	0.967	0.986	0.953	0.980	1.000	0.967	1.000	0.967	1.017		
16	6.00	0.968	1.007	0.968	0.987	0.955	0.980	1.000	0.967	1.000	0.967	1.017		
17	8.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000		
18	10.00	0.981	1.004	0.981	0.992	0.973	0.988	1.000	0.980	1.000	0.980	1.010		
19	12.00	0.988	1.003	0.988	0.995	0.983	0.993	1.000	0.988	1.000	0.988	1.006		
20	14.00	1.002	1.000	1.002	1.001	1.002	1.001	1.000	1.002	1.000	1.002	0.999		
21	16.00	1.006	0.999	1.006	1.002	1.009	1.004	1.000	1.006	1.000	1.006	0.997		
22	18.00	0.996	1.001	0.996	0.998	0.994	0.997	1.000	0.995	1.000	0.995	1.002		
23	20.00	1.005	0.999	1.005	1.002	1.007	1.003	1.000	1.005	1.000	1.005	0.998		
24	22.00	0.970	1.006	0.970	0.988	0.958	0.982	1.000	0.970	1.000	0.970	1.016		
25	24.00	0.796	1.050	0.796	0.911	0.723	0.870	1.002	0.793	1.002	0.793	1.125		

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2240, STATION -12 inches

MACH = 14.19 P0 = 20100. psia T0 = 2660. degF PTAvg = 12.66 psia

MACH	NOMINAL FREESTREAM CONDITIONS										
	QINF psia	TINF degR	PINF psia	REINF 1/ft	UINF ft/sec	RHOINF lbm/ft3	VIP ft**1/2				
14.19	6.871	89.0	4.88E-02	4.10E+06	6673.	1.43E-03	7.01E-03				
Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL					RE	U	RHO	VIP
			M	Q	T	P					
1	-24.00	0.498	1.154	0.499	0.755	0.374	0.654	1.003	0.496	1.427	
2	-22.00	0.733	1.066	0.733	0.882	0.645	0.828	1.001	0.731	1.172	
3	-20.00	0.919	1.018	0.919	0.966	0.887	0.950	1.000	0.918	1.044	
4	-18.00	0.991	1.002	0.991	0.996	0.988	0.995	1.000	0.991	1.004	
5	-16.00	0.998	1.000	0.998	0.999	0.997	0.999	1.000	0.998	1.001	
6	-14.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.002	
7	-12.00	0.994	1.001	0.994	0.997	0.991	0.996	1.000	0.994	1.003	
8	-10.00	0.984	1.003	0.984	0.994	0.978	0.990	1.000	0.984	1.008	
9	-8.00	0.979	1.004	0.979	0.992	0.971	0.987	1.000	0.979	1.011	
10	-6.00	0.981	1.004	0.981	0.992	0.973	0.988	1.000	0.981	1.010	
11	-4.00	0.963	1.008	0.963	0.985	0.948	0.977	1.000	0.963	1.020	
12	-2.00	0.964	1.008	0.964	0.985	0.949	0.978	1.000	0.963	1.019	
13	0.00	0.916	1.018	0.916	0.965	0.884	0.948	1.000	0.916	1.046	
14	2.00	0.953	1.010	0.953	0.981	0.934	0.971	1.000	0.952	1.025	
15	4.00	0.977	1.005	0.977	0.991	0.968	0.986	1.000	0.977	1.012	
16	6.00	0.980	1.004	0.980	0.992	0.972	0.988	1.000	0.980	1.010	
17	8.00	0.978	1.005	0.978	0.991	0.969	0.986	1.000	0.978	1.012	
18	10.00	0.983	1.002	0.983	0.995	0.983	0.993	1.000	0.988	1.006	
19	12.00	0.996	1.001	0.996	0.998	0.994	0.998	1.000	0.996	1.002	
20	14.00	1.005	0.999	1.005	1.002	1.007	1.003	1.000	1.005	0.998	
21	16.00	1.002	1.000	1.002	1.001	1.003	1.001	1.000	1.002	0.999	
22	18.00	0.998	1.000	0.998	0.999	0.998	0.999	1.000	0.998	1.001	
23	20.00	0.944	1.012	0.944	0.977	0.922	0.965	1.000	0.943	1.030	
24	22.00	0.771	1.055	0.772	0.901	0.693	0.854	1.001	0.770	1.142	
25	24.00	0.524	1.143	0.524	0.770	0.401	0.674	1.003	0.521	1.391	

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2241, STATION 72 inches

MACH = 14.16 P0 = 19500. psia T0 = 2880. degF PTAvg = 11.79 psia

MACH	QINF psia	NOMINAL FREESTREAM CONDITIONS						RHOINF lbm/ft3	VIP ft**1/2
		TINF degR	PINF psia	REINF 1/ft	UINF ft/sec				
14.16	6.398	95.8	4.56E-02	3.43E+06	6908.			1.24E-03	7.64E-03
Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL							
		PT	M	Q	T	P	RE	U	RHO VIP
1	-24.00	0.545	1.133	0.545	0.783	0.424	0.691	1.003	0.542 1.364
2	-22.00	0.737	1.065	0.737	0.884	0.650	0.830	1.001	0.735 1.169
3	-20.00	0.948	1.011	0.948	0.979	0.928	0.968	1.000	0.948 1.028
4	-18.00	1.011	0.998	1.011	1.004	1.016	1.007	1.000	1.011 0.994
5	-16.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000 1.000
6	-14.00	0.996	1.001	0.996	0.998	0.994	0.997	1.000	0.996 1.002
7	-12.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.985 1.007
8	-10.00	0.993	1.001	0.993	0.997	0.990	0.996	1.000	0.993 1.003
9	-8.00	0.963	1.008	0.963	0.985	0.948	0.977	1.000	0.962 1.020
10	-6.00	0.963	1.008	0.963	0.985	0.948	0.977	1.000	0.962 1.020
11	-4.00	0.957	1.009	0.957	0.982	0.939	0.973	1.000	0.956 1.023
12	-2.00	0.966	1.007	0.966	0.986	0.952	0.979	1.000	0.966 1.018
13	0.00	0.962	1.008	0.962	0.984	0.947	0.977	1.000	0.961 1.020
14	2.00	0.981	1.004	0.981	0.992	0.974	0.989	1.000	0.981 1.010
15	4.00	0.961	1.008	0.961	0.984	0.945	0.976	1.000	0.961 1.021
16	6.00	0.970	1.006	0.970	0.988	0.958	0.982	1.000	0.970 1.016
17	8.00	0.970	1.006	0.970	0.988	0.958	0.982	1.000	0.970 1.016
18	10.00	0.997	1.001	0.997	0.999	0.995	0.998	1.000	0.997 1.002
19	12.00	1.001	1.000	1.001	1.000	1.001	1.001	1.000	1.001 1.000
20	14.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000 0.000
21	16.00	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000 0.000
22	18.00	1.015	0.997	1.015	1.006	1.022	1.009	1.000	1.015 0.992
23	20.00	0.967	1.007	0.967	0.987	0.954	0.980	1.000	0.967 1.017
24	22.00	0.761	1.058	0.761	0.896	0.680	0.847	1.001	0.759 1.150
25	24.00	0.556	1.128	0.557	0.789	0.437	0.700	1.003	0.554 1.349

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2242, STATION 48 inches

MACH = 14.30 P0 = 19750. psia T0 = 2610. degF PTAvg = 12.03 psia

MACH	NOMINAL FREESTREAM CONDITIONS				RHOINF lbm/ft3	VIP ft**1/2
	QINF psia	TINF degr	PINF psia	REINF 1/ft	UINF ft/sec	
14.30	6.532	86.0	4.56E-02	4.06E+06	6614.	1.38E-03 7.09E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
		PT	M	Q	T	P	RE							
1	-24.00	0.525	1.142	0.526	0.771	0.403	0.676	1.003	0.523	1.389				
2	-22.00	0.765	1.057	0.765	0.897	0.685	0.849	1.001	0.763	1.147				
3	-20.00	0.943	1.012	0.943	0.977	0.921	0.965	1.000	0.943	1.030				
4	-18.00	1.004	0.999	1.004	1.002	1.005	1.002	1.000	1.004	0.998				
5	-16.00	1.004	0.999	1.004	1.002	1.005	1.002	1.000	1.004	0.998				
6	-14.00	0.996	1.001	0.996	0.998	0.995	0.998	1.000	0.996	1.002				
7	-12.00	0.995	1.001	0.995	0.998	0.994	0.997	1.000	0.995	1.002				
8	-10.00	0.990	1.002	0.990	0.996	0.985	0.994	1.000	0.989	1.005				
9	-8.00	1.014	0.997	1.014	1.006	1.019	1.008	1.000	1.014	0.993				
10	-6.00	0.971	1.006	0.971	0.988	0.960	0.982	1.000	0.971	1.015				
11	-4.00	0.948	1.011	0.948	0.979	0.927	0.968	1.000	0.948	1.028				
12	-2.00	0.949	1.011	0.949	0.979	0.929	0.969	1.000	0.948	1.027				
13	0.00	0.912	1.019	0.912	0.963	0.877	0.945	1.000	0.911	1.049				
14	2.00	0.929	1.015	0.929	0.971	0.901	0.956	1.000	0.928	1.038				
15	4.00	0.952	1.010	0.952	0.980	0.933	0.971	1.000	0.952	1.025				
16	6.00	0.967	1.007	0.967	0.987	0.954	0.980	1.000	0.967	1.017				
17	8.00	1.001	1.000	1.001	1.001	1.002	1.001	1.000	1.001	0.999				
18	10.00	1.013	0.997	1.013	1.005	1.018	1.008	1.000	1.013	0.993				
19	12.00	1.000	1.000	1.000	1.000	1.001	1.000	1.000	1.000	1.000				
20	14.00	0.994	1.001	0.994	0.997	0.991	0.996	1.000	0.994	1.003				
21	16.00	0.996	1.001	0.996	0.998	0.995	0.998	1.000	0.996	1.002				
22	18.00	1.005	0.999	1.005	1.002	1.008	1.003	1.000	1.005	0.997				
23	20.00	0.951	1.011	0.951	0.980	0.931	0.970	1.000	0.950	1.026				
24	22.00	0.787	1.051	0.787	0.908	0.713	0.864	1.001	0.786	1.130				
25	24.00	0.534	1.138	0.535	0.777	0.413	0.683	1.003	0.532	1.377				

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2243, STATION 24 inches

MACH = 14.45 P0 = 20200. psia T0 = 2375. degF PTAvg = 12.38 psia

MACH	QINF psia	TINF degF	NOMINAL FREESTREAM CONDITIONS				RHOINF lbm/ft3	VIP ft**1/2
			PINF psia	REINF 1/ft	UINF ft/sec			
14.45	6.716	77.7	4.59E-02	4.81E+06	6353.	1.54E-03	6.59E-03	

Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
			M	Q	T	P	RE								
1	-24.00	0.526	1.141	0.526	0.772	0.404	0.676	1.003	0.523	1.388					
2	-22.00	0.740	1.064	0.740	0.886	0.653	0.832	1.001	0.738	1.166					
3	-20.00	0.927	1.016	0.927	0.970	0.898	0.955	1.000	0.926	1.040					
4	-18.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	0.999					
5	-16.00	1.004	0.999	1.004	1.001	1.005	1.002	1.000	1.004	0.998					
6	-14.00	1.008	0.998	1.008	1.003	1.012	1.005	1.000	1.009	0.996					
7	-12.00	0.996	1.001	0.996	0.998	0.994	0.997	1.000	0.996	1.002					
8	-10.00	1.004	0.999	1.004	1.001	1.005	1.002	1.000	1.004	0.998					
9	-8.00	1.000	1.000	1.000	1.000	0.999	1.000	1.000	1.000	1.000					
10	-6.00	1.013	0.997	1.013	1.005	1.018	1.008	1.000	1.013	0.994					
11	-4.00	0.961	1.008	0.961	0.984	0.945	0.976	1.000	0.960	1.021					
12	-2.00	0.925	1.016	0.925	0.969	0.896	0.954	1.000	0.925	1.040					
13	0.00	0.905	1.021	0.905	0.961	0.869	0.941	1.000	0.904	1.052					
14	2.00	0.925	1.016	0.925	0.969	0.896	0.954	1.000	0.925	1.040					
15	4.00	0.946	1.011	0.946	0.978	0.925	0.967	1.000	0.946	1.029					
16	6.00	1.002	1.000	1.002	1.001	1.003	1.001	1.000	1.002	0.999					
17	8.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	0.999					
18	10.00	1.009	0.998	1.009	1.004	1.013	1.006	1.000	1.009	0.995					
19	12.00	1.009	0.998	1.009	1.004	1.013	1.006	1.000	1.009	0.995					
20	14.00	1.005	0.999	1.005	1.002	1.007	1.003	1.000	1.005	0.997					
21	16.00	0.996	1.001	0.996	0.999	0.995	0.998	1.000	0.996	1.002					
22	18.00	1.013	0.997	1.013	1.005	1.019	1.008	1.000	1.013	0.993					
23	20.00	0.954	1.010	0.954	0.981	0.935	0.971	1.000	0.953	1.025					
24	22.00	0.773	1.055	0.773	0.901	0.695	0.855	1.001	0.771	1.141					
25	24.00	0.547	1.132	0.547	0.784	0.427	0.693	1.003	0.544	1.361					

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2244, STATION 12 inches

MACH = 14.42 P0 = 20200. psia T0 = 2375. degF PTAvg = 12.51 psia

MACH	QINF psia	TINF degR	NOMINAL FREESTREAM CONDITIONS					RHOINF lbm/ft3	VIP ft**1/2
			PINF psia	REINF 1/ft	UINF ft/sec	U	RHO		
14.42	6.790	78.1	4.67E-02	4.84E+06	6353.	1.56E-03	6.56E-03		

Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL							
			M	Q	T	P	RE	U	RHO	VIP
1	-24.00	0.520	1.144	0.521	0.769	0.398	0.672	1.003	0.518	1.395
2	-22.00	0.734	1.066	0.734	0.883	0.646	0.828	1.001	0.732	1.171
3	-20.00	0.922	1.017	0.922	0.968	0.891	0.952	1.000	0.921	1.043
4	-18.00	0.998	1.000	0.998	0.999	0.998	0.999	1.000	0.998	1.001
5	-16.00	1.004	0.999	1.004	1.002	1.006	1.002	1.000	1.004	0.998
6	-14.00	1.002	1.000	1.002	1.001	1.003	1.001	1.000	1.002	0.999
7	-12.00	0.996	1.001	0.996	0.998	0.994	0.998	1.000	0.996	1.002
8	-10.00	0.998	1.000	0.998	0.999	0.998	0.999	1.000	0.998	1.001
9	-8.00	0.994	1.001	0.994	0.998	0.992	0.997	1.000	0.994	1.003
10	-6.00	0.987	1.003	0.987	0.995	0.932	0.992	1.000	0.987	1.007
11	-4.00	0.972	1.006	0.972	0.989	0.961	0.983	1.000	0.972	1.015
12	-2.00	0.922	1.017	0.922	0.968	0.891	0.952	1.000	0.921	1.043
13	0.00	0.917	1.018	0.917	0.966	0.885	0.949	1.000	0.916	1.045
14	2.00	0.921	1.017	0.921	0.967	0.890	0.951	1.000	0.920	1.043
15	4.00	0.953	1.010	0.953	0.981	0.934	0.971	1.000	0.952	1.025
16	6.00	0.986	1.003	0.986	0.994	0.981	0.992	1.000	0.986	1.007
17	8.00	0.999	1.000	0.999	1.000	0.999	1.000	1.000	0.999	1.000
18	10.00	0.998	1.000	0.998	0.999	0.997	0.999	1.000	0.998	1.001
19	12.00	1.007	0.999	1.007	1.003	1.010	1.004	1.000	1.007	0.996
20	14.00	1.002	1.000	1.002	1.001	1.003	1.001	1.000	1.002	0.999
21	16.00	0.996	1.001	0.996	0.998	0.994	0.998	1.000	0.996	1.002
22	18.00	1.006	0.999	1.006	1.002	1.008	1.003	1.000	1.006	0.997
23	20.00	0.950	1.011	0.950	0.980	0.931	0.970	1.000	0.950	1.026
24	22.00	0.764	1.057	0.764	0.897	0.684	0.849	1.001	0.762	1.147
25	24.00	0.532	1.139	0.533	0.776	0.411	0.681	1.003	0.530	1.379

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2247, STATION 0 inches

MACH = 10.43 P0 = 13500. psia T0 = 1220. degF PTAvg = 45.71 psia

MACH	QINF psia	NOMINAL FREESTREAM CONDITIONS					VIP ft**1/2
		TINF degR	PINF psia	REINF 1/ft	UINF ft/sec	RHOINF lbm/ft3	
10.43	24.767	81.9	3.25E-01	2.28E+07	4704.	1.04E-02	2.19E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
		PT	M	Q	T	P	RE							
1	-24.00	0.749	1.063	0.749	0.889	0.662	0.838	1.003	0.745	1.161				
2	-22.00	0.957	1.009	0.957	0.982	0.940	0.974	1.000	0.957	1.023				
3	-20.00	1.008	0.998	1.008	1.003	1.012	1.005	1.000	1.008	0.996				
4	-18.00	0.998	1.000	0.998	0.999	0.998	0.999	1.000	0.998	1.001				
5	-16.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.003				
6	-14.00	0.983	1.004	0.983	0.993	0.976	0.990	1.000	0.983	1.009				
7	-12.00	0.998	1.000	0.998	0.999	0.997	0.999	1.000	0.998	1.001				
8	-10.00	0.998	1.000	0.998	0.999	0.998	0.999	1.000	0.998	1.001				
9	-8.00	1.008	0.998	1.008	1.003	1.011	1.005	1.000	1.008	0.996				
10	-6.00	1.019	0.996	1.019	1.006	1.027	1.011	1.000	1.019	0.990				
11	-4.00	1.024	0.995	1.024	1.010	1.035	1.015	1.000	1.025	0.988				
12	-2.00	1.045	0.991	1.045	1.018	1.065	1.027	1.000	1.046	0.977				
13	0.00	1.046	0.990	1.046	1.018	1.066	1.028	1.000	1.047	0.977				
14	2.00	1.049	0.990	1.049	1.020	1.071	1.030	1.000	1.050	0.975				
15	4.00	1.037	0.992	1.037	1.015	1.053	1.022	1.000	1.038	0.981				
16	6.00	1.022	0.995	1.022	1.009	1.032	1.014	1.000	1.023	0.989				
17	8.00	1.001	1.000	1.001	1.000	1.001	1.000	1.000	1.001	1.000				
18	10.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000				
19	12.00	0.721	1.072	0.722	0.876	0.628	0.819	1.003	0.718	1.184				
20	14.00	0.986	1.003	0.986	0.994	0.980	0.991	1.000	0.985	1.007				
21	16.00	0.992	1.002	0.992	0.997	0.989	0.995	1.000	0.992	1.004				
22	18.00	1.002	1.000	1.002	1.001	1.002	1.001	1.000	1.002	0.999				
23	20.00	1.011	0.998	1.011	1.004	1.015	1.006	1.000	1.011	0.995				
24	22.00	1.002	1.000	1.002	1.001	1.003	1.001	1.000	1.002	0.999				
25	24.00	0.824	1.042	0.824	0.924	0.759	0.889	1.002	0.822	1.105				

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1605, RUN 2248, STATION 24 inches

MACH = 10.45 P0 = 14000. psia T0 = 1255. degF PTAvg = 47.14 psia

MACH	QINF psia	TINF degr	NOMINAL FREESTREAM CONDITIONS					RHOINF lbm/ft3	VIP ft**1/2	
			PINF psia	REINF 1/ft	UINF ft/sec	RHOINF lbm/ft3	VIP ft**1/2			
10.45	25.542	83.6	3.34E-01	2.27E+07	4762.	1.04E-02	2.19E-03			
Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL					U	RHO	VI
			M	Q	T	P	RE			
1	-24.00	0.702	1.078	0.703	0.866	0.605	0.806	1.003	0.698	1.200
2	-22.00	0.913	1.020	0.913	0.964	0.879	0.946	1.001	0.912	1.048
3	-20.00	0.984	1.003	0.984	0.994	0.978	0.990	1.000	0.984	1.000
4	-18.00	0.993	1.002	0.993	0.997	0.990	0.996	1.000	0.993	1.000
5	-16.00	0.988	1.002	0.988	0.995	0.984	0.993	1.000	0.988	1.000
6	-14.00	0.995	1.001	0.995	0.998	0.992	0.997	1.000	0.994	1.000
7	-12.00	0.996	1.001	0.996	0.998	0.994	0.997	1.000	0.996	1.000
8	-10.00	0.998	1.000	0.998	0.999	0.997	0.999	1.000	0.998	1.000
9	-8.00	0.996	1.001	0.997	0.999	0.995	0.998	1.000	0.996	1.000
10	-6.00	0.997	1.001	0.997	0.999	0.996	0.998	1.000	0.997	1.000
11	-4.00	0.997	1.001	0.997	0.999	0.995	0.998	1.000	0.997	1.000
12	-2.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	0.999
13	0.00	0.993	1.002	0.993	0.997	0.990	0.996	1.000	0.993	1.000
14	2.00	1.004	0.999	1.004	1.002	1.006	1.003	1.000	1.004	0.999
15	4.00	1.007	0.998	1.007	1.003	1.010	1.004	1.000	1.007	0.999
16	6.00	1.010	0.998	1.010	1.004	1.014	1.006	1.000	1.010	0.999
17	8.00	1.009	0.998	1.009	1.004	1.013	1.005	1.000	1.009	0.999
18	10.00	1.009	0.998	1.009	1.004	1.013	1.006	1.000	1.010	0.999
19	12.00	1.010	0.998	1.010	1.004	1.015	1.006	1.000	1.010	0.999
20	14.00	1.003	0.999	1.003	1.001	1.004	1.002	1.000	1.003	0.999
21	16.00	1.005	0.999	1.005	1.002	1.008	1.003	1.000	1.006	0.999
22	18.00	1.007	0.998	1.007	1.003	1.010	1.004	1.000	1.007	0.999
23	20.00	1.007	0.999	1.007	1.003	1.010	1.004	1.000	1.007	0.999
24	22.00	0.971	1.006	0.972	0.988	0.960	0.983	1.000	0.971	1.015
25	24.00	0.782	1.053	0.783	0.905	0.705	0.861	1.002	0.779	1.135

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2259, STATION 66 inches

MACH = 10.37 P0 = 14250. psia T0 = 1320. degF PTAvg = 49.10 psia

MACH	QINF psia	TINF degF	NOMINAL FREESTREAM CONDITIONS					RHOINF lbm/ft3	VIP ft**1/2
			PINF psia	REINF 1/ft	UINF ft/sec				
10.37	26.603	88.2	3.53E-01	2.20E+07	4858.			1.04E-02	2.21E-03
Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL						
			M	Q	T	P	RE	U	VIP
1	-24.00	0.705	1.077	0.706	0.868	0.609	0.808	1.003	0.701
2	-22.00	0.873	1.029	0.873	0.946	0.824	0.920	1.001	0.871
3	-20.00	0.986	1.003	0.986	0.994	0.980	0.992	1.000	0.986
4	-18.00	1.002	1.000	1.002	1.001	1.003	1.001	1.000	1.002
5	-16.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
6	-14.00	0.997	1.001	0.997	0.999	0.996	0.998	1.000	0.997
7	-12.00	0.993	1.001	0.993	0.997	0.991	0.996	1.000	0.993
8	-10.00	0.987	1.003	0.987	0.995	0.981	0.992	1.000	0.986
9	-8.00	0.988	1.003	0.988	0.995	0.983	0.993	1.000	0.988
10	-6.00	0.981	1.004	0.981	0.992	0.972	0.988	1.000	0.980
11	-4.00	0.975	1.005	0.975	0.990	0.965	0.985	1.000	0.975
12	-2.00	0.960	1.009	0.960	0.984	0.944	0.976	1.000	0.960
13	0.00	0.954	1.010	0.954	0.981	0.935	0.971	1.000	0.953
14	2.00	0.959	1.009	0.959	0.983	0.942	0.975	1.000	0.958
15	4.00	0.971	1.006	0.971	0.988	0.959	0.982	1.000	0.971
16	6.00	0.969	1.007	0.969	0.987	0.956	0.981	1.000	0.968
17	8.00	0.969	1.007	0.969	0.987	0.956	0.981	1.000	0.968
18	10.00	0.979	1.005	0.979	0.991	0.970	0.987	1.000	0.978
19	12.00	0.986	1.003	0.986	0.994	0.981	0.992	1.000	0.986
20	14.00	0.990	1.002	0.990	0.996	0.985	0.994	1.000	0.990
21	16.00	0.993	1.002	0.993	0.997	0.990	0.996	1.000	0.993
22	18.00	0.998	1.000	0.998	0.999	0.997	0.999	1.000	0.998
23	20.00	0.984	1.003	0.984	0.994	0.978	0.990	1.000	0.984
24	22.00	0.873	1.029	0.873	0.946	0.824	0.920	1.001	0.871
25	24.00	0.740	1.066	0.740	0.885	0.651	0.832	1.003	0.736

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2260, STATION 108 inches

MACH = 10.43 P0 = 14100. psia T0 = 1300. degF PTAvg = 47.33 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degr psia 1/ft ft/sec lbm/ft3 ft**1/2

10.43 25.645 86.1 3.36E-01 2.18E+07 4829. 1.02E-02 2.23E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL									
		PT	M	Q	T	P	RE	U	RHO	VIP	
1	-24.00	0.742	1.065	0.743	0.886	0.654	0.834	1.003	0.739	1.166	
2	-22.00	0.885	1.026	0.885	0.951	0.840	0.928	1.001	0.883	1.065	
3	-20.00	0.934	1.015	0.934	0.973	0.907	0.959	1.001	0.933	1.036	
4	-18.00	0.931	1.015	0.931	0.971	0.903	0.957	1.001	0.929	1.038	
5	-16.00	1.018	0.996	1.018	1.007	1.026	1.011	1.000	1.019	0.991	
6	-14.00	1.038	0.992	1.037	1.015	1.054	1.023	1.000	1.038	0.981	
7	-12.00	1.027	0.994	1.026	1.011	1.038	1.016	1.000	1.027	0.987	
8	-10.00	1.017	0.996	1.017	1.007	1.025	1.010	1.000	1.018	0.994	
9	-8.00	1.011	0.998	1.011	1.004	1.016	1.007	1.000	1.011	0.994	
10	-6.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	
11	-4.00	1.005	0.999	1.005	1.002	1.007	1.003	1.000	1.005	0.998	
12	-2.00	1.009	0.998	1.009	1.004	1.013	1.005	1.000	1.009	0.995	
13	0.00	1.016	0.997	1.016	1.006	1.022	1.009	1.000	1.016	0.992	
14	2.00	0.998	1.001	0.998	0.999	0.997	0.999	1.000	0.998	1.001	
15	4.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.003	
16	6.00	0.986	1.003	0.986	0.994	0.980	0.992	1.000	0.986	1.007	
17	8.00	0.997	1.001	0.997	0.999	0.996	0.998	1.000	0.997	1.002	
18	10.00	1.001	1.000	1.001	1.000	1.001	1.000	1.000	1.001	1.000	
19	12.00	1.008	0.998	1.007	1.003	1.011	1.005	1.000	1.008	0.996	
20	14.00	1.020	0.996	1.020	1.008	1.029	1.012	1.000	1.021	0.990	
21	16.00	0.982	1.004	0.982	0.993	0.974	0.989	1.000	0.981	1.010	
22	18.00	0.919	1.018	0.919	0.966	0.887	0.950	1.001	0.918	1.045	
23	20.00	0.907	1.021	0.907	0.961	0.870	0.942	1.001	0.905	1.052	
24	22.00	0.858	1.033	0.858	0.940	0.804	0.911	1.001	0.856	1.082	
25	24.00	0.727	1.070	0.727	0.878	0.635	0.823	1.003	0.723	1.179	

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2261, STATION 108 inches

MACH = 13.17 P0 = 2100. psia T0 = 2475. degF PTAvg = 1.53 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degR psia 1/ft ft/sec lbm/ft3 ft*1/2

13.17 0.829 90.0 6.83E-03 5.24E+05 6233. 1.98E-04 1.82E-02

NOMINAL FREESTREAM CONDITIONS

PROFILES NORMALIZED TO NOMINAL

Probe #	Dist. from center (in)	PT	M	Q	T	P	RE	U	RHO	VIP
1	-24.00	0.381	1.221	0.381	0.677	0.256	0.556	1.005	0.378	1.638
2	-22.00	0.551	1.131	0.552	0.786	0.431	0.696	1.003	0.548	1.356
3	-20.00	0.742	1.064	0.742	0.886	0.656	0.834	1.002	0.740	1.165
4	-18.00	0.909	1.020	0.909	0.962	0.873	0.943	1.001	0.908	1.050
5	-16.00	0.985	1.003	0.985	0.994	0.979	0.991	1.000	0.985	1.008
6	-14.00	1.005	0.999	1.005	1.002	1.007	1.003	1.000	1.005	0.997
7	-12.00	0.970	1.006	0.970	0.988	0.957	0.981	1.000	0.969	1.016
8	-10.00	0.929	1.015	0.929	0.971	0.901	0.956	1.000	0.928	1.038
9	-8.00	0.924	1.016	0.924	0.969	0.895	0.953	1.000	0.924	1.041
10	-6.00	0.917	1.018	0.917	0.966	0.885	0.949	1.000	0.916	1.045
11	-4.00	0.898	1.023	0.898	0.957	0.858	0.936	1.001	0.897	1.057
12	-2.00	0.892	1.024	0.892	0.955	0.850	0.933	1.001	0.891	1.060
13	0.00	0.894	1.023	0.894	0.956	0.854	0.934	1.001	0.893	1.059
14	2.00	0.898	1.023	0.898	0.958	0.859	0.937	1.001	0.897	1.057
15	4.00	0.902	1.022	0.902	0.959	0.864	0.939	1.001	0.901	1.054
16	6.00	0.914	1.019	0.914	0.964	0.880	0.947	1.001	0.913	1.047
17	8.00	0.930	1.015	0.930	0.971	0.903	0.957	1.000	0.930	1.038
18	10.00	0.931	1.015	0.931	0.972	0.904	0.957	1.000	0.930	1.037
19	12.00	0.973	1.006	0.973	0.989	0.962	0.983	1.000	0.973	1.014
20	14.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.003
21	16.00	0.962	1.008	0.962	0.984	0.946	0.977	1.000	0.961	1.020
22	18.00	0.884	1.026	0.884	0.951	0.840	0.928	1.001	0.883	1.065
23	20.00	0.749	1.062	0.749	0.890	0.665	0.839	1.002	0.747	1.159
24	22.00	0.572	1.123	0.572	0.798	0.454	0.712	1.003	0.569	1.331
25	24.00	0.386	1.217	0.386	0.681	0.260	0.560	1.005	0.383	1.627

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2262, STATION 24 inches

MACH = 13.21 P0 = 2100. psia T0 = 2400. degF PTAvg = 1.52 psia
 MACH QINF TINF PINF REINF UINF RHOINF VIP
 psia degR psia 1/ft ft/sec lbm/ft3 ft**1/2
 13.21 0.825 87.0 6.75E-03 5.47E+05 6145. 2.02E-04 1.79E-02

NOMINAL FREESTREAM CONDITIONS

PROFILES NORMALIZED TO NOMINAL

Probe #	Dist. from center (in)	PT	M	Q	T	P	RE	U	RHO	VIP
1	-24.00	0.360	1.235	0.360	0.662	0.236	0.537	1.005	0.357	1.686
2	-22.00	0.554	1.130	0.554	0.788	0.434	0.698	1.003	0.550	1.353
3	-20.00	0.796	1.049	0.796	0.912	0.724	0.870	1.001	0.794	1.124
4	-18.00	0.955	1.010	0.955	0.981	0.936	0.972	1.000	0.954	1.024
5	-16.00	0.996	1.001	0.996	0.998	0.994	0.998	1.000	0.996	1.002
6	-14.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
7	-12.00	0.997	1.001	0.997	0.999	0.996	0.998	1.000	0.997	1.001
8	-10.00	0.968	1.007	0.968	0.987	0.955	0.980	1.000	0.967	1.017
9	-8.00	0.963	1.008	0.963	0.985	0.948	0.977	1.000	0.963	1.019
10	-6.00	0.976	1.005	0.976	0.990	0.967	0.986	1.000	0.976	1.012
11	-4.00	0.964	1.008	0.965	0.985	0.950	0.978	1.000	0.964	1.019
12	-2.00	1.007	0.999	1.007	1.003	1.010	1.004	1.000	1.007	0.996
13	0.00	1.043	0.991	1.043	1.017	1.061	1.026	1.000	1.043	0.979
14	2.00	1.003	0.999	1.003	1.001	1.005	1.002	1.000	1.003	0.998
15	4.00	0.962	1.008	0.962	0.984	0.946	0.977	1.000	0.961	1.020
16	6.00	0.959	1.009	0.959	0.983	0.943	0.975	1.000	0.959	1.022
17	8.00	0.995	1.001	0.995	0.998	0.993	0.997	1.000	0.995	1.002
18	10.00	0.982	1.004	0.982	0.993	0.975	0.989	1.000	0.982	1.009
19	12.00	0.999	1.000	0.999	0.999	0.998	0.999	1.000	0.999	1.001
20	14.00	1.009	0.998	1.009	1.004	1.013	1.006	1.000	1.009	0.995
21	16.00	1.004	0.999	1.004	1.002	1.006	1.002	1.000	1.004	0.998
22	18.00	0.959	1.009	0.959	0.983	0.943	0.975	1.000	0.959	1.022
23	20.00	0.822	1.041	0.823	0.924	0.759	0.888	1.001	0.821	1.105
24	22.00	0.570	1.123	0.571	0.797	0.452	0.710	1.003	0.567	1.333
25	24.00	0.351	1.241	0.351	0.656	0.228	0.529	1.005	0.348	1.707

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2264, STATION 66 inches

MACH = 13.10 P0 = 2250. psia T0 = 2550. degF PTAvg = 1.67 psia

MACH	NOMINAL FREESTREAM CONDITIONS							PROFILES NORMALIZED TO NOMINAL								
	QINF psia	TINF degR	PINF psia	REINF 1/ft	UINF ft/sec	RHOINF lbm/ft3	VIP ft**1/2	PT	M	Q	T	P	RE	U	RHO	VIP
13.10	0.905	93.6	7.53E-03	5.43E+05	6320.	2.10E-04	1.78E-02									
Probe #	Dist. from center (in)															
1	-24.00	0.345	1.245	0.346	0.651	0.223	0.523	1.005	0.342	1.721						
2	-22.00	0.518	1.146	0.518	0.767	0.395	0.670	1.003	0.515	1.400						
3	-20.00	0.751	1.061	0.751	0.891	0.667	0.840	1.002	0.749	1.158						
4	-18.00	0.971	1.006	0.971	0.988	0.959	0.982	1.000	0.971	1.015						
5	-16.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000						
6	-14.00	0.956	1.009	0.956	0.982	0.938	0.973	1.000	0.955	1.023						
7	-12.00	0.940	1.013	0.940	0.975	0.917	0.963	1.000	0.940	1.032						
8	-10.00	0.929	1.015	0.929	0.971	0.901	0.956	1.000	0.928	1.039						
9	-8.00	0.910	1.020	0.910	0.962	0.875	0.944	1.001	0.909	1.050						
10	-6.00	0.931	1.015	0.931	0.972	0.904	0.958	1.000	0.931	1.037						
11	-4.00	0.945	1.012	0.945	0.977	0.922	0.966	1.000	0.944	1.030						
12	-2.00	0.948	1.011	0.948	0.979	0.927	0.968	1.000	0.948	1.028						
13	0.00	0.926	1.016	0.926	0.969	0.897	0.954	1.000	0.925	1.040						
14	2.00	0.934	1.014	0.934	0.973	0.908	0.959	1.000	0.933	1.036						
15	4.00	0.950	1.011	0.950	0.979	0.930	0.969	1.000	0.949	1.027						
16	6.00	0.938	1.013	0.938	0.974	0.913	0.962	1.000	0.937	1.033						
17	8.00	0.936	1.014	0.936	0.973	0.910	0.960	1.000	0.935	1.035						
18	10.00	0.938	1.013	0.938	0.974	0.913	0.962	1.000	0.937	1.033						
19	12.00	0.949	1.011	0.949	0.979	0.929	0.969	1.000	0.949	1.027						
20	14.00	0.957	1.009	0.957	0.972	0.940	0.974	1.000	0.957	1.023						
21	16.00	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000						
22	18.00	0.980	1.004	0.980	0.992	0.972	0.988	1.000	0.980	1.010						
23	20.00	0.768	1.056	0.768	0.899	0.688	0.851	1.001	0.766	1.145						
24	22.00	0.535	1.138	0.535	0.777	0.413	0.683	1.003	0.532	1.377						
25	24.00	0.349	1.243	0.350	0.654	0.226	0.527	1.005	0.346	1.712						

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2265, STATION 66 inches

MACH = 13.70 P0 = 9250. psia T0 = 2700. degF PTAvg = 5.96 psia

MACH	NOMINAL FREESTREAM CONDITIONS					RHOINF lbm/ft3	VIP ft**1/2			
	QINF psia	TINF degr	PINF psia	REINF 1/ft	UINF ft/sec					
13.70	3.234	92.8	2.46E-02	1.88E+06	6583.	6.91E-04	1.00E-02			
Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL					U	RHO	VIP
			M	Q	T	P	RE			
1	-24.00	0.471	1.168	0.472	0.738	0.346	0.632	1.003	0.468	1.469
2	-22.00	0.677	1.084	0.677	0.854	0.577	0.789	1.002	0.675	1.221
3	-20.00	0.893	1.024	0.893	0.955	0.853	0.934	1.001	0.892	1.055
4	-18.00	0.983	1.004	0.983	0.993	0.976	0.990	1.000	0.983	1.000
5	-16.00	0.994	1.001	0.994	0.998	0.992	0.996	1.000	0.994	1.000
6	-14.00	0.982	1.004	0.982	0.993	0.975	0.989	1.000	0.982	1.000
7	-12.00	0.971	1.006	0.971	0.988	0.960	0.982	1.000	0.971	1.015
8	-10.00	0.970	1.006	0.970	0.988	0.958	0.982	1.000	0.970	1.016
9	-8.00	0.945	1.012	0.945	0.977	0.923	0.966	1.000	0.945	1.022
10	-6.00	0.953	1.010	0.953	0.981	0.934	0.971	1.000	0.952	1.022
11	-4.00	0.961	1.008	0.961	0.984	0.945	0.976	1.000	0.960	1.022
12	-2.00	0.988	1.003	0.988	0.995	0.982	0.992	1.000	0.987	1.000
13	0.00	0.990	1.002	0.990	0.996	0.987	0.994	1.000	0.990	1.000
14	2.00	0.993	1.001	0.993	0.997	0.991	0.996	1.000	0.993	1.000
15	4.00	0.962	1.008	0.962	0.985	0.947	0.977	1.000	0.962	1.022
16	6.00	0.964	1.008	0.964	0.985	0.949	0.978	1.000	0.963	1.019
17	8.00	0.966	1.007	0.966	0.986	0.952	0.979	1.000	0.965	1.018
18	10.00	0.980	1.004	0.980	0.992	0.972	0.988	1.000	0.980	1.010
19	12.00	0.976	1.005	0.976	0.990	0.967	0.986	1.000	0.976	1.010
20	14.00	1.010	0.998	1.010	1.004	1.015	1.006	1.000	1.010	0.995
21	16.00	1.006	0.999	1.006	1.002	1.008	1.004	1.000	1.006	0.997
22	18.00	0.998	1.000	0.998	0.999	0.998	0.999	1.000	0.998	1.000
23	20.00	0.916	1.018	0.916	0.965	0.883	0.948	1.000	0.915	1.046
24	22.00	0.702	1.076	0.702	0.867	0.607	0.806	1.002	0.700	1.198
25	24.00	0.475	1.166	0.475	0.740	0.349	0.635	1.003	0.472	1.463

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2266, STATION 24 inches

MACH = 14.25 P0 = 19500. psia T0 = 2680. degF PTAvg = 11.87 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degR psia 1/ft ft/sec lbm/ft3 ft**1/2

14.25 6.442 88.6 4.53E-02 3.85E+06 6689. 1.33E-03 7.26E-03

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										RE	U	RHO	VIP
		PT	M	Q	T	P									
1	-24.00	0.568	1.124	0.568	0.796	0.450						0.708	1.003	0.565	1.335
2	-22.00	0.784	1.051	0.784	0.907	0.709						0.862	1.001	0.783	1.132
3	-20.00	0.955	1.010	0.955	0.981	0.936						0.972	1.000	0.954	1.024
4	-18.00	1.001	1.000	1.001	1.000	1.001						1.001	1.000	1.001	1.000
5	-16.00	1.002	1.000	1.002	1.001	1.002						1.001	1.000	1.002	0.999
6	-14.00	0.997	1.001	0.997	0.999	0.996						0.998	1.000	0.997	1.001
7	-12.00	0.997	1.001	0.997	0.999	0.996						0.998	1.000	0.997	1.001
8	-10.00	0.998	1.000	0.998	0.999	0.998						0.999	1.000	0.998	1.001
9	-8.00	1.000	1.000	1.000	1.000	1.000						1.000	1.000	1.000	1.000
10	-6.00	0.992	1.002	0.992	0.997	0.988						0.995	1.000	0.991	1.004
11	-4.00	0.959	1.009	0.959	0.983	0.942						0.975	1.000	0.958	1.022
12	-2.00	0.952	1.010	0.952	0.980	0.933						0.970	1.000	0.952	1.025
13	0.00	0.918	1.018	0.918	0.966	0.887						0.949	1.000	0.918	1.045
14	2.00	0.929	1.015	0.929	0.971	0.901						0.956	1.000	0.929	1.038
15	4.00	0.951	1.010	0.951	0.980	0.932						0.970	1.000	0.951	1.026
16	6.00	0.983	1.004	0.983	0.993	0.976						0.990	1.000	0.983	1.009
17	8.00	1.005	0.999	1.005	1.002	1.007						1.003	1.000	1.005	0.997
18	10.00	1.016	0.997	1.016	1.006	1.023						1.010	1.000	1.016	0.992
19	12.00	1.001	1.000	1.001	1.000	1.001						1.001	1.000	1.001	1.000
20	14.00	0.996	1.001	0.996	0.998	0.994						0.997	1.000	0.996	1.002
21	16.00	0.998	1.000	0.998	0.999	0.998						0.999	1.000	0.998	1.001
22	18.00	1.000	1.000	1.000	1.000	1.000						1.000	1.000	1.000	1.000
23	20.00	0.956	1.009	0.956	0.982	0.939						0.973	1.000	0.956	1.023
24	22.00	0.812	1.044	0.812	0.919	0.745						0.881	1.001	0.810	1.113
25	24.00	0.575	1.121	0.575	0.800	0.458						0.714	1.002	0.572	1.326

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2267, STATION 24 inches

MACH = 13.70 P0 = 8750. psia T0 = 2500. degF PTAvg = 5.79 psia

MACH	QINF psia	NOMINAL FREESTREAM CONDITIONS					RHOINF lbm/ft ³	VIP ft**1/2
		TINF degR	PINF psia	REINF 1/ft	UINF ft/sec			
13.70	3.139	86.4	2.39E-02	2.03E+06	6350.	7.21E-04	9.63E-03	

Probe #	Dist. from center (in)	PROFILES NORMALIZED TO NOMINAL										U	RHO	VIP
		PT	M	Q	T	P	RE							
1	-24.00	0.482	1.162	0.483	0.745	0.357	0.642					1.003	0.479	1.451
2	-22.00	0.695	1.078	0.695	0.863	0.598	0.801					1.002	0.693	1.204
3	-20.00	0.897	1.023	0.898	0.957	0.858	0.936					1.001	0.897	1.057
4	-18.00	0.995	1.001	0.995	0.998	0.993	0.997					1.000	0.995	1.002
5	-16.00	0.995	1.001	0.995	0.998	0.993	0.997					1.000	0.995	1.003
6	-14.00	0.985	1.003	0.985	0.994	0.979	0.991					1.000	0.985	1.008
7	-12.00	0.989	1.002	0.989	0.996	0.985	0.993					1.000	0.989	1.006
8	-10.00	0.990	1.002	0.990	0.996	0.986	0.994					1.000	0.990	1.005
9	-8.00	0.982	1.004	0.982	0.992	0.974	0.989					1.000	0.981	1.010
10	-6.00	0.983	1.004	0.983	0.993	0.976	0.990					1.000	0.983	1.009
11	-4.00	0.960	1.009	0.960	0.984	0.944	0.975					1.000	0.959	1.021
12	-2.00	0.957	1.009	0.957	0.982	0.939	0.973					1.000	0.956	1.023
13	0.00	0.905	1.021	0.905	0.960	0.868	0.941					1.001	0.904	1.053
14	2.00	0.927	1.016	0.927	0.970	0.898	0.955					1.000	0.926	1.040
15	4.00	0.957	1.009	0.957	0.982	0.939	0.973					1.000	0.956	1.023
16	6.00	0.976	1.005	0.977	0.990	0.967	0.986					1.000	0.976	1.012
17	8.00	0.987	1.003	0.987	0.995	0.982	0.992					1.000	0.987	1.007
18	10.00	1.009	0.998	1.009	1.004	1.013	1.006					1.000	1.009	0.995
19	12.00	1.006	0.999	1.006	1.003	1.009	1.004					1.000	1.006	0.997
20	14.00	0.996	1.001	0.996	0.998	0.994	0.997					1.000	0.995	1.002
21	16.00	1.005	0.999	1.005	1.002	1.007	1.003					1.000	1.005	0.997
22	18.00	1.014	0.997	1.014	1.005	1.019	1.008					1.000	1.014	0.993
23	20.00	0.917	1.018	0.917	0.966	0.885	0.949					1.000	0.916	1.045
24	22.00	0.713	1.072	0.714	0.873	0.621	0.814					1.002	0.711	1.189
25	24.00	0.482	1.162	0.483	0.745	0.357	0.642					1.003	0.479	1.451

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2268, STATION 108 inches

MACH = 14.35 P0 = 20000. psia T0 = 2700. degF PTAvg = 11.82 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degr psia 1/ft ft/sec lbm/ft3 ft**1/2

14.35 6.418 88.2 4.46E-02 3.84E+06 6718. 1.32E-03 7.32E-03

Probe #	Dist. from center (in)	PT	PROFILES NORMALIZED TO NOMINAL							U	RHO	VIP
			M	Q	T	P	RE					
1	-24.00	0.583	1.118	0.583	0.804	0.467	0.720	1.002	0.580	1.317		
2	-22.00	0.766	1.057	0.766	0.898	0.686	0.850	1.001	0.764	1.146		
3	-20.00	0.901	1.022	0.901	0.959	0.863	0.938	1.001	0.900	1.055		
4	-18.00	0.992	1.002	0.992	0.997	0.989	0.995	1.000	0.992	1.004		
5	-16.00	1.009	0.998	1.009	1.004	1.013	1.005	1.000	1.009	0.995		
6	-14.00	1.004	0.999	1.004	1.002	1.005	1.002	1.000	1.004	0.998		
7	-12.00	0.978	1.005	0.978	0.991	0.968	0.986	1.000	0.977	1.012		
8	-10.00	0.960	1.009	0.960	0.984	0.944	0.975	1.000	0.959	1.021		
9	-8.00	0.960	1.009	0.960	0.984	0.944	0.975	1.000	0.959	1.021		
10	-6.00	0.965	1.007	0.965	0.986	0.951	0.978	1.000	0.965	1.018		
11	-4.00	0.978	1.005	0.978	0.991	0.968	0.986	1.000	0.977	1.012		
12	-2.00	0.995	1.001	0.995	0.998	0.992	0.997	1.000	0.994	1.003		
13	0.00	0.978	1.005	0.978	0.991	0.970	0.987	1.000	0.978	1.011		
14	2.00	0.981	1.004	0.981	0.992	0.973	0.988	1.000	0.981	1.010		
15	4.00	0.998	1.000	0.998	0.999	0.997	0.999	1.000	0.998	1.001		
16	6.00	0.973	1.006	0.973	0.989	0.961	0.983	1.000	0.972	1.014		
17	8.00	0.967	1.007	0.967	0.987	0.954	0.980	1.000	0.967	1.017		
18	10.00	0.962	1.008	0.962	0.985	0.947	0.977	1.000	0.962	1.020		
19	12.00	0.978	1.005	0.978	0.991	0.970	0.987	1.000	0.978	1.011		
20	14.00	0.996	1.001	0.996	0.998	0.995	0.998	1.000	0.996	1.002		
21	16.00	1.016	0.997	1.016	1.006	1.022	1.009	1.000	1.016	0.992		
22	18.00	0.979	1.004	0.979	0.992	0.971	0.987	1.000	0.979	1.011		
23	20.00	0.898	1.022	0.898	0.958	0.859	0.937	1.001	0.897	1.056		
24	22.00	0.779	1.053	0.779	0.904	0.703	0.859	1.001	0.778	1.136		
25	24.00	0.583	1.117	0.583	0.805	0.467	0.720	1.002	0.581	1.317		

TUNNEL 9 FLOW UNIFORMITY CALIBRATION
WTR 1608, RUN 2269, STATION 108 inches

MACH = 13.68 P0 = 9500. psia T0 = 2650. degF PTAvg = 6.24 psia

MACH QINF TINF PINF REINF UINF RHOINF VIP

 psia degr psia 1/ft ft/sec lbm/ft3 ft**1/2

13.68 3.389 91.7 2.59E-02 2.01E+06 6530. 7.36E-04 9.65E-03

NOMINAL FREESTREAM CONDITIONS

PROFILES NORMALIZED TO NOMINAL

Probe #	Dist. from center (in)	PT	M	Q	T	P	RE	U	RHO	VIP
1	-24.00	0.494	1.157	0.494	0.752	0.369	0.651	1.003	0.491	1.434
2	-22.00	0.667	1.087	0.667	0.849	0.565	0.782	1.002	0.665	1.230
3	-20.00	0.860	1.032	0.860	0.941	0.807	0.912	1.001	0.858	1.081
4	-18.00	0.979	1.004	0.979	0.992	0.971	0.987	1.000	0.979	1.011
5	-16.00	0.999	1.000	0.999	1.000	0.998	0.999	1.000	0.999	1.001
6	-14.00	0.980	1.004	0.980	0.992	0.971	0.988	1.000	0.971	1.011
7	-12.00	0.952	1.008	0.962	0.984	0.947	0.977	1.000	0.962	1.020
8	-10.00	0.940	1.013	0.940	0.975	0.917	0.963	1.000	0.940	1.032
9	-8.00	0.939	1.013	0.939	0.975	0.915	0.962	1.000	0.939	1.033
10	-6.00	0.950	1.011	0.950	0.980	0.930	0.969	1.000	0.950	1.026
11	-4.00	0.960	1.009	0.960	0.983	0.943	0.975	1.000	0.959	1.021
12	-2.00	0.965	1.007	0.965	0.986	0.951	0.978	1.000	0.965	1.018
13	0.00	0.942	1.012	0.942	0.976	0.919	0.964	1.000	0.941	1.031
14	2.00	0.958	1.009	0.958	0.983	0.941	0.974	1.000	0.957	1.022
15	4.00	0.982	1.004	0.982	0.993	0.974	0.989	1.000	0.982	1.009
16	6.00	0.961	1.008	0.961	0.984	0.946	0.976	1.000	0.961	1.020
17	8.00	0.953	1.010	0.953	0.981	0.935	0.971	1.000	0.953	1.025
18	10.00	0.952	1.010	0.952	0.980	0.933	0.971	1.000	0.952	1.025
19	12.00	0.970	1.006	0.970	0.988	0.958	0.982	1.000	0.970	1.016
20	14.00	0.981	1.004	0.981	0.992	0.974	0.989	1.000	0.981	1.010
21	16.00	1.001	1.000	1.001	1.000	1.002	1.001	1.000	1.001	0.999
22	18.00	0.991	1.002	0.991	0.996	0.987	0.994	1.000	0.990	1.005
23	20.00	0.878	1.027	0.879	0.949	0.833	0.924	1.001	0.877	1.069
24	22.00	0.692	1.079	0.692	0.862	0.594	0.799	1.002	0.689	1.208
25	24.00	0.493	1.157	0.493	0.752	0.368	0.650	1.003	0.490	1.436

DISTRIBUTION

Copies

DOD ACTIVITIES (CONUS)

DEFENSE TECHNICAL
INFORMATION CENTER
CAMERON STATION
ALEXANDRIA VA 22304-6145 12

ATTN CODE E29L 4
COASTAL SYSTEMS STATION
DAHLGREN DIVISION
NAVAL SURFACE WARFARE CENTER
6703 WEST HIGHWAY 98
PANAMA CITY FL 32407-7001

NON-DOD ACTIVITIES

ATTN GIFT AND EXCHANGE DIV 4
LIBRARY OF CONGRESS
WASHINGTON DC 20540

CENTER FOR NAVAL ANALYSES
4401 FORD AVENUE
ALEXANDRIA VA 22302-0268 1

NATIONAL AEROSPACE PLANE
JOINT PROGRAM OFFICE
WRIGHT PATTERSON AFB
OH 45433 1

INTERNAL

E231 2
E232 3
K24 1
K24 (D MARREN) 1

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE 31 January 1994		3. REPORT TYPE AND DATES COVERED	
4. TITLE AND SUBTITLE Hypervelocity Tunnel 9 Mach 10/14 Calibration				5. FUNDING NUMBERS	
6. AUTHOR(S) Dan Marren					
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Naval Surface Warfare Center (Code K24) 10901 New Hampshire Avenue Silver Spring, MD 20903-5640				8. PERFORMING ORGANIZATION REPORT NUMBER NSWCDD/TR-92/160	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES					
12a. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited.				12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) This report documents the Tunnel 9 Mach 10/14 Calibration test program (WTR 1608) performed at the Naval Surface Warfare Center, White Oak, Maryland. This effort was sponsored by the National Aerospace Plane Joint Program Office (NASP JPO). Free stream flow field parameter distributions were obtained for both the Mach 10 and 14 nozzles spanning the Reynolds number range. A total of four Mach 10, and ten Mach 14 runs were performed during this test program. The test period was 7 to 22 May 1991. Results from this test entry were combined with previous test data in the final analysis. Data from the test reveal that high quality uniform flow exists and that deviations in core flow field parameters are comparable with the calibration data taken in the past.					
14. SUBJECT TERMS Hypervelocity Wind Tunnel Uniformity Calibration				15. NUMBER OF PAGES 66	
				16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT UNCLASSIFIED	20. LIMITATION OF ABSTRACT UL		

GENERAL INSTRUCTIONS FOR COMPLETING SF 298

The Report Documentation Page (RDP) is used in announcing and cataloging reports. It is important that this information be consistent with the rest of the report, particularly the cover and its title page. Instructions for filling in each block of the form follow. It is important to *stay within the lines* to meet *optical scanning requirements*.

Block 1. Agency Use Only (Leave blank).

Block 2. Report Date. Full publication date including day, month, and year, if available (e.g. 1 Jan 88). Must cite at least the year.

Block 3. Type of Report and Dates Covered. State whether report is interim, final, etc. If applicable, enter inclusive report dates (e.g. 10 Jun 87 - 30 Jun 88).

Block 4. Title and Subtitle. A title is taken from the part of the report that provides the most meaningful and complete information. When a report is prepared in more than one volume, repeat the primary title, add volume number, and include subtitle for the specific volume. On classified documents enter the title classification in parentheses.

Block 5. Funding Numbers. To include contract and grant numbers; may include program element number(s), project number(s), task number(s), and work unit number(s). Use the following labels:

C - Contract	PR - Project
G - Grant	TA - Task
PE - Program Element	WU - Work Unit Accession No.

BLOCK 6. Author(s). Name(s) of person(s) responsible for writing the report, performing the research, or credited with the content of the report. If editor or compiler, this should follow the name(s).

Block 7. Performing Organization Name(s) and Address(es). Self-explanatory.

Block 8. Performing Organization Report Number. Enter the unique alphanumeric report number(s) assigned by the organization performing the report.

Block 9. Sponsoring/Monitoring Agency Name(s) and Address(es). Self-explanatory.

Block 10. Sponsoring/Monitoring Agency Report Number. (If Known)

Block 11. Supplementary Notes. Enter information not included elsewhere such as: Prepared in cooperation with...; Trans. of...; To be published in... When a report is revised, include a statement whether the new report supersedes or supplements the older report.

Block 12a. Distribution/Availability Statement.

Denotes public availability or limitations. Cite any availability to the public. Enter additional limitations or special markings in all capitals (e.g. NOFORN, REL, ITAR).

DOD - See DoDD 5230.24, "Distribution Statements on Technical Documents."
DOE - See authorities.
NASA - See Handbook NHB 2200.2
NTIS - Leave blank.

Block 12b. Distribution Code.

DOD - Leave blank.
DOE - Enter DOE distribution categories from the Standard Distribution for Unclassified Scientific and Technical Reports.
NASA - Leave blank.
NTIS - Leave blank.

Block 13. Abstract. Include a brief (*Maximum 200 words*) factual summary of the most significant information contained in the report.

Block 14. Subject Terms. Keywords or phrases identifying major subjects in the report.

Block 15. Number of Pages. Enter the total number of pages.

Block 16. Price Code. Enter appropriate price code (*NTIS only*)

Blocks 17.-19. Security Classifications. Self-explanatory. Enter U.S. Security Classification in accordance with U.S. Security Regulations (i.e., UNCLASSIFIED) If form contains classified information, stamp classification on the top and bottom of the page.

Block 20. Limitation of Abstract. This block must be completed to assign a limitation to the abstract. Enter either UL (unlimited) or SAR (same as report). An entry in this block is necessary if the abstract is to be limited. If blank, the abstract is assumed to be unlimited.